

AD-A109 797

METCALF AND EDDY OF NEW YORK INC NY

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. LITTLE CHOCONUT WATERSHED SITE 2C --ETC(U)

SEP 81 G P FULTON


DACW51-81-C-0044


NL

UNCLASSIFIED

1 of 2

AD A  
16-87-1





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

SUSQUEHANNA RIVER BASIN

2

LITTLE CHOCONUT WATERSHED SITE 2C DAM

BROOME COUNTY, NEW YORK  
INVENTORY NO. NY, 722

LEVEL II

AD A109797

**PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**

**APPROVED FOR PUBLIC RELEASE  
DISTRIBUTION UNLIMITED**

**DTIC**  
ELECTE  
JAN 20 1982  
S E



**NEW YORK DISTRICT CORPS OF ENGINEERS**

**AUGUST 1981**

DTIC FILE COPY

2

01 19 82 060

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A109 777	
4. TITLE (and Subtitle)		5. TYPE OF REPORT & PERIOD COVERED
Phase I Inspection Report Little Choconut Watershed Site 2c Dam Oswego River Basin, Broome County, NY Inventory No. 722		Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s)		6. PERFORMING ORG. REPORT NUMBER
GEORGE P. FULTON		
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
Metcalf and Eddy of New York, Inc., 60 East 42nd Street New York, New York 100017		DACW51-81-C-0044
11. CONTROLLING OFFICE NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
Department of the Army 26 Federal Plaza New York District, CofE New York, New York 10287		
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE
Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		14 September 1981
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report)
		UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)		
Approved for public release; Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)		
Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Little Choconut Watershed Site 2c Dam Oswego River Basin Broome County		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)		
This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.  The examination of documents and a visual inspection of The Little Choconut Watershed Site 2C Dam did not reveal conditions which constitute a hazard to human life or property.		

The total discharge capacity of the spillways is adequate to impound and safely discharge the floodwaters resulting from the Probable Maximum Flood (PMF).

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, and Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For	
PHASE I	<input checked="checked" type="checkbox"/>
PHASE II	<input type="checkbox"/>
Unassessed	<input type="checkbox"/>
Justification	
By	
District	
Approved	
or	
Dist	Special
A	

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
LITTLE CHOCONUT WATERSHED SITE 2C DAM  
I.D. No. NY-722  
(#96A-3619)  
SUSQUEHANNA RIVER BASIN  
BROOME COUNTY, NEW YORK  
TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	
- OVERVIEW PHOTOGRAPH	
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	4
2.1 GEOTECHNICAL DATA	4
2.2 DESIGN RECORDS	4
2.3 CONSTRUCTION RECORDS	5
2.4 OPERATION RECORDS	5
2.5 EVALUATION OF DATA	5
3 VISUAL INSPECTION	6
3.1 FINDINGS	6
3.2 EVALUATION OF OBSERVATIONS	7
4 OPERATION AND MAINTENANCE PROCEDURES	8
4.1 PROCEDURES	8
4.2 MAINTENANCE OF DAM	8
4.3 WARNING SYSTEM IN EFFECT	8
4.4 EVALUATION	8
5 HYDROLOGIC/HYDRAULIC	9

	<u>PAGE NO.</u>
5.1 DRAINAGE AREA CHARACTERISTICS	9
5.2 ANALYSIS CRITERIA	9
5.3 SPILLWAY CAPACITY	9
5.4 RESERVOIR CAPACITY	9
5.5 FLOODS OF RECORD	9
5.6 OVERTOPPING POTENTIAL	9
5.7 EVALUATION	10
6 STRUCTURAL STABILITY	11
6.1 EVALUATION OF STRUCTURAL STABILITY	11
7 ASSESSMENT/RECOMMENDATIONS	12
7.1 ASSESSMENT	12
7.2 RECOMMENDED MEASURES	12

#### APPENDIX

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC: ENGINEERING DATA AND COMPUTATIONS
- D. STABILITY COMPUTATIONS
- E. REFERENCES
- F. PREVIOUS INSPECTION REPORTS
- G. DRAWINGS



Phase I Inspection Report  
National Dam Safety Program

Name of Dam: Little Choconut Watershed Site 2C Dam  
I.D. No. NY-722

State Located: New York

County Located: Broome

Watershed: Susquehanna River Basin

Date of Inspection: July 10, 1981


ASSESSMENT:


The examination of documents and a visual inspection of The Little Choconut Watershed Site 2C Dam did not reveal conditions which constitute a hazard to human life or property.

The total discharge capacity of the spillways is adequate to impound and safely discharge the floodwaters resulting from the Probable Maximum Flood (PMF).


Several minor deficiencies were noted which should be corrected within six months of the date of final approval of this report.

The required actions are mowing the crown vetch on the dam and in the auxiliary spillway, repair areas eroded by vehicular traffic, replace missing planking from the top of the inlet riser, lubricate the slide gate stem, repair the animal guard on the internal drainage pipe, and visually monitor wet areas along the toe of the east slope of the auxiliary spillway. In addition, an emergency action plan for notification of downstream residents should be developed within the same time frame.

  
Edward M. Greco, P.E.  
Project Manager  
Metcalf & Eddy of New York, Inc.  
New York Registration No. A7463

  
George P. Fulton, P.E.  
Vice President  
Metcalf & Eddy of New York, Inc.  
New York Registration No. 22390

Approved By:

  
Col. W. M. Smith, Jr.  
New York District Engineer

Date:

14 Sep 81

OVERVIEW  
LITTLE CHOCONUT WATERSHED  
SITE 2C DAM  
ID NO. NY 722



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
LITTLE CHOCONUT WATERSHED SITE 2C DAM  
I.D. No. NY-722  
(#96A-3619)  
SUSQUEHANNA RIVER BASIN  
BROOME COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam

The Little Choconut Watershed Site 2C Dam consists of an earth dam with a service spillway pipe passing through the embankment and an excavated auxiliary spillway passing around the eastern end of the dam.

The dam consists of a compacted earth embankment which is 59 feet high, has a crest length of 590 feet and a crest width of 19 feet. The upstream slope is 1 vertical on 3 horizontal with a 10 foot wide berm near the base of the slope. The downstream slope is 1 vertical on 2.5 horizontal. The crest and exposed slopes are covered with crown vetch. An earth cutoff trench of varying depth and width keys the embankment into the foundation soils.

The service spillway consists of a rectangular reinforced concrete drop inlet structure, a 30 inch diameter reinforced concrete pipe with anti-seepage collars and a concrete impact basin. A reservoir drain consisting of a 12 inch diameter cast iron pipe extends 45 feet upstream from the base of the spillway riser to an excavated 10 foot wide inlet channel. A vertical slide gate mechanism mounted along the inside of the riser controls the flow through the reservoir drain. The auxiliary spillway is an earth cut with a bottom width of 160 feet.

The internal drainage system consists of twin 10-inch bituminous coated perforated corrugated metal pipes in a drain fill trench located downstream of the centerline of the dam, symmetric about the service spillway and approximately parallel with the downstream toe. Seepage is conducted through these drains to discharge in the concrete impact basin

beyond the baffle structure.

b. Location

The Little Choconut Watershed Site 2C Dam is located off New Ireland Road in the Town of Maine. The structure is approximately 0.25 miles north of the Village of New Ireland.

c. Size Classification

The dam is 59 feet high and has a maximum storage capacity of almost 1,400 acre-feet. Therefore, the dam is in the intermediate size category as defined by the "Recommended Guidelines for Safety Inspection of Dams."

d. Hazard Classification

This dam is classified as "high" hazard due to the presence of a number of homes in the Village of New Ireland located downstream of the dam.

e. Ownership

The dam is owned by Broome County, New York. Mr. Darrell Stone, Broome County, Deputy Commissioner of Public Works was contacted; telephone number is (607) 772-2871.

f. Purpose of Dam

The dam is a floodwater retarding structure.

g. Design and Construction History

The dam was designed by the U.S. Department of Agriculture, Soil Conservation Service (SCS). The SCS district office in Syracuse has a design folder containing hydrologic, hydraulic and structural design information. Dam construction was performed by Les Strong, Inc. and was completed in 1968.

h. Normal Operating Procedures

Normal flows are discharged through the service spillway. This structure has sufficient capacity to store and discharge a 100 year flood without discharge occurring in the auxiliary spillway. For storms in excess of the 100 year flood, discharge through the auxiliary spillway can be expected.

1.3 PERTINENT DATA

a. Drainage Area (square miles)

3.5

b. Discharge at Dam (cfs)

Service Spillway at maximum high water	145
Service Spillway at auxiliary spillway crest elev.	132
Auxiliary Spillway at maximum high water	15,685
Reservoir drain at service spillway crest elevation	14.3

c. Elevation (USGS Datum)

Top of Dam	1241.0
Auxiliary Spillway Crest	1231.1
Service Spillway Crest	1199.8
Reservoir Drain (invert elevation)	1185.0

d. Reservoir Surface Area (acres)

Top of Dam	62.8
Auxiliary Spillway Crest	47.3
Service Spillway Crest	5.7

e. Storage Capacity (acre-feet)

Top of Dam	1,271
Auxiliary Spillway Crest	733
Service Spillway Crest	0

f. Dam

Embankment type - A compacted earth fill with a keyed earth cut-off trench, and a drain parallel to the axis of dam

Embankment length (ft)	590
------------------------	-----

Slopes - Upstream	1 vertical on 3.0 horizontal with 10 foot wide berm - slope below berm is 1 vertical on 3 horizontal
Downstream	1 vertical on 2.5 horizontal

Crest Width (ft)	19
------------------	----

g. Service Spillway

Type: Ungated, reinforced concrete drop inlet (2.5 x 7.5 ft), rising 19 feet above the invert of the 30 inch diameter concrete conduit; length of conduit 284.33 feet

Weir length (ft).	13.3
-------------------	------

h. Auxiliary Spillway

Type: An excavated, trapezoidal channel with a crown vetch lining.

Bottom Width (ft)	160
Side Slopes (V:H)	1:2.5, 1:3.0
Exit Slope (ft/ft)	0.028

i. Reservoir Drain

Type: 12 inch diameter cast iron pipe

Control: Manually operated vertical slide gate mounted along the inside of the service spillway riser.

## SECTION 2: ENGINEERING DATA

### 2.1 GEOTECHNICAL DATA

#### a. Geology

The Little Choconut Watershed Site 2C Dam is located in the Allegheny Plateau Physiographic Province of southern New York State. It is approximately 4 miles north of Johnson City. The moderately steep slopes on the site are typical of the glacial topography of the area. There is no bedrock exposed anywhere on the site, and none was encountered in any of the drill holes or test pits. Approximately 1.5 miles north of Site 2-C, along the New Ireland Road, siltstone and shale (a shaly siltstone) of the Upper Devonian period outcrop along the roadside.

The till deposits in the Binghamton area have been classified as two facies of the Wisconsin glacial movement. It has been suggested by at least one author that the Binghamton facies will not be found at elevations above 950'. This would indicate that the material on this site would be classified as the Olean facies of the Wisconsin glacial period.

There is a thin layer (approx, 2' - 3') of recent alluvial material which overlies the glacial till across the flood plain.

Some of the tills located in the flood plain, below the recent alluvium, appear to have been reworked in some way, causing a lower percent of fines to be associated with this material. However, it still classifies as a GM material.

#### b. Subsurface Investigations

A subsurface investigation program was conducted by SCS. Test pits and drill holes were progressed in 1965. A total of 18 borings and 17 test pits were taken at locations along the dam auxiliary spillway and structural elements. Applicable subsurface information has been included in Appendix F.

In order to penetrate the denser till, an average excavation depth of five feet was recommended for the principal spillway. Material from the auxiliary spillway was determined to be uniform and capable of providing a homogeneous embankment material. Bedrock was not encountered in any of the test holes. Testing of the samples taken indicated a significant percentage of fines in the till and subsequently a low permeability rate.

### 2.2 DESIGN RECORDS

This dam was designed by the Soil Conservation Service, who prepared a design report. A folder containing the design report and other design information was available at the SCS district office in Syracuse. Eighteen drawings, several of which have been included in Appendix F, were prepared for the construction of this dam.

### 2.3 CONSTRUCTION RECORDS

Complete construction records are available from the SCS office in Syracuse. The construction drawings in Appendix are noted to be as-built record drawings.

### 2.4 OPERATION RECORDS

Since the dam is an uncontrolled, floodwater retarding structure, no operating records are maintained regarding water levels. However, during periods of heavy rainfall, SCS personnel do monitor reservoir levels.

### 2.5 EVALUATION OF DATA

The data presented in this report has been compiled from information obtained from the Soil Conservation Service as well as the New York State Department of Environmental Conservation files. It appears to be adequate and reliable for Phase I inspection purposes.

## SECTION 3: VISUAL INSPECTION

### 3.1 FINDINGS

#### a. General

Visual inspection of the Site 1 dam was conducted on July 10, 1981. The weather was partly cloudy and the temperature was in the eighties. The water surface at the time of the inspection was at the weir crest of the concrete riser.

#### b. Embankment

No signs of distress were observed in the earth embankment and no evidence of seepage, misalignment, subsidence or surface cracking were noted on the embankment. The only deficiencies noted were of a minor nature. Consideration should be given to mowing all embankment slopes as the crown vetch averages 3 feet in height. Minor erosion mainly due to vehicular traffic present on the top of the dam and on the upstream slope at the west abutment.

An internal drainage system composed of 2 - 10 inch diameter pipes surrounded by drain-fill material provides drainage at the base of the embankment. At the time of the inspection, there was no flow coming from the pipes. The outlet ends of the drainage pipes are covered by small animal guards. The guard for the outlet on the west side of the impact basin has been vandalized.

#### c. Service Spillway

The service spillway consists of a vertical drop inlet structure, a reinforced concrete pipe and reinforced concrete impact basin at the conduit outlet. The elements which were visible appeared to be in good condition. One section of galvanized planking was missing from the top of the inlet riser. Minor rust was visible on the trash racks, planking, slide gate stem, and the bolts for the metal work. Minor staining of the concrete was noted in the impact basin.

#### d. Auxiliary Spillway

The auxiliary spillway is located in an earth cut at the eastern end of the dam. A 3-foot high growth of crown vetch covers the channel and side slopes. Erosion due to vehicular traffic exists on the crest and side slopes. Wet areas with cattails occur along the toe of the east side slope. The spillway discharges into a natural wooded area.

#### e. Reservoir Drain

The 12 inch diameter reservoir drain and manually operated slide gate may be used to lower the reservoir. The drain was reported to be operational.

#### f. Reservoir

There were no signs of serious soil instability in the reservoir area.



g. Downstream Channel

The downstream channel below the impact basin was stone filled for a distance. Beyond the area which was disturbed by construction, the channel was cut into natural ground. Heavy brush and some trees were growing along the edge of the channel.

3.2 EVALUATION OF OBSERVATIONS

Visual inspection of this dam revealed the following deficiencies:

1. The 3-foot high crown vetch cover on all features of the dam and auxiliary spillway hindered a more thorough visual inspection;
2. Erosion of the vegetative cover due to vehicular traffic on the top and upstream slope of the dam and in the channel and side slopes of the auxiliary spillway;
3. A section of galvanized planking missing from the top of the inlet riser;
4. Minor rust on the gate stem on the low-level outlet;
5. A vandalized animal guard on the west outlet of the internal drainage system;
6. Wet areas along the toe of the west side slope of the auxiliary spillways.

## SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

### 4.1 PROCEDURES

The normal water surface elevation is at the crest of the principal spillway riser. Downstream flows are limited by flow into the riser, except during periods of extremely heavy runoff when the auxiliary spillway is in service.

### 4.2 MAINTENANCE OF DAM

The dam is maintained by the owner. Yearly technical inspections are conducted by Broome County Personnel. Construction of the dam was completed in 1968. Consideration should be given to mowing the top and slopes of the dam as well as the channels and slopes of the auxiliary spillway. The dam appeared to be satisfactorily maintained.

### 4.3 WARNING SYSTEM IN EFFECT

Notification of the local civil defense agent is the only warning system in use at this time. A system for notification of residents downstream of the dam is currently being investigated by Broome County.

### 4.4 EVALUATION

The operation and maintenance procedures for this dam are satisfactory.

## SECTION 5: HYDROLOGIC/HYDRAULIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

Delineation of the 3.5 square mile watershed of the Site 1 dam was made using the USGS 7.5 minute quadrangle for Castle Creek, New York. The watershed consists of open grassed fields and woodlands. Relief in the drainage area ranges from moderate to steep.

### 5.2 ANALYSIS CRITERIA

The analysis of the floodwater retarding capability of this dam was performed using the Corps of Engineers HEC-1 computer program, Dam Safety version. This program develops an inflow hydrograph using the Snyder Synthetic Unit Hydrograph method and then uses the "Modified Puls" flood routing procedure. The spillway design flood selected was the Probable Maximum Flood (PMF) in accordance with the Recommended Guidelines of the U.S. Army Corps of Engineers.

### 5.3 SPILLWAY CAPACITY

The principal and auxiliary spillways are uncontrolled structures. The capacities for both spillways were taken from the stage-discharge data included in the SCS design report.

The spillways have sufficient capacity for discharging the peak outflow from the PMF. For this storm, the peak inflow is 5,814 cfs and the peak outflow is 5,716 cfs. When the spillways are discharging the peak outflow, the water surface will be 4.4 feet below the top of the dam. Further information concerning this analysis is included in Appendix C.

### 5.4 RESERVOIR CAPACITY

Normal flood control storage capacity of the reservoir between the principal and auxiliary spillways is 733 acre-feet which is equivalent to a runoff depth of 3.94 inches over the drainage area. Surge storage capacity to the maximum high water elevation is an additional 538 acre-feet, equivalent to a runoff depth over the drainage area of 2.89 inches. Total storage capacity of the dam is 1,271 acre-feet.

### 5.5 FLOODS OF RECORD

The maximum known flood occurred during September, 1975. The pool level at this time was reported to be about elevation 1217.6. No higher water has been recorded since the dam was completed in 1968.

### 5.6 OVERTOPPING POTENTIAL

Analysis indicates that the total discharge capacity is sufficient to prevent overtopping from the PMF.

#### 5.7 EVALUATION

This dam has sufficient capability to impound and adequately discharge floodwaters expected to result from the PMF.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

No signs of distress were observed in connection with the earth embankment.

#### b. Design and Construction Data

Design data was obtained from SCS (see Appendix D Stability Computations). Stability analyses were performed using the Swedish circle method of analysis. Two undrained triaxial shear tests were performed on compacted soil samples from the auxiliary spillway excavation. These tests were used to select soil parameters for use in the analysis. One case was analyzed on the upstream slope. For rapid drawdown from the permanent pool elevation, considering a 10' berm at elevation 1199.8 and a 1 on 3 slope, the minimum factor of safety was 1.53. For the downstream slope, long term steady seepage was analyzed. The minimum factor of safety for this case was 1.86.

#### c. Post Construction Changes

There have been no changes in the construction of the dam since it was completed in 1968.

#### d. Seismic Stability

The dam is located in Seismic Zone 1. No records of any seismic stability analysis performed for this structure could be located.

## SECTION 7: ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Safety

The Phase I inspection of the Little Choconut Watershed Site 2C Dam did not reveal conditions which constitute a hazard to human life or property. The earth embankment is considered to be stable and the spillways are capable of retarding and safely discharging floodwaters resulting from the Probable Maximum Flood (PMF).

#### b. Adequacy of Information

Information reviewed for Phase I inspection purposes is considered to be adequate.

#### c. Need for Additional Investigations

No additional investigations are necessary at this time.

#### d. Urgency

Remedial measures listed below should be completed by the Owner within 6 months of the date of final approval of this report.

### 7.2 RECOMMENDED MEASURES

The following actions should be taken within six months of the date of final approval of this report:

- a. Mow the crown vetch cover to facilitate future inspection evaluations.
- b. Repair areas eroded by vehicular traffic and consider methods to limit further trespass.
- c. Replace missing planking on top of the inlet riser.
- d. Lubricate the slide gate stem to insure continued operability.
- e. Repair the animal guard on the internal drainage pipe.
- f. Visually monitor the wet areas along the toe of the east side slope of the auxiliary spillway. If increased seepage causes instability of the slope, install horizontal drains into the hillside.
- g. Develop an emergency action plan for notification of downstream residents in the event of large auxiliary spillway discharges.

APPENDIX A

PHOTOGRAPHS



UPSTREAM SLOPE OF DAM



TOP OF DAM AND TIRE TRACKS





DOWNSTREAM SLOPE OF DAM AND OUTLET AT TOE




DISCHARGE CHANNEL BELOW OUTLET



**INTAKE STRUCTURE (FOREGROUND) AND APPROACH  
CHANNEL OF EMERGENCY SPILLWAY (BACKGROUND)**



**EMERGENCY SPILLWAY CHANNEL NEAR CREST**



OUTLET STRUCTURE



OUTLET END OF DISCHARGE PIPE



TIRE TRACKS ON UPSTREAM SLOPE AT RIGHT ABUTMENT



TRESPASSING ON CREST AND SIDES OF EMERGENCY  
SPILLWAY

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST1) Basic Data

## a. General

Name of Dam LITTLE CHOCONUT WATERSHED SITE 2C DAMFed. I.D. # NY 722 DEC Dam No. 96A-3619River Basin SUSQUEHANNALocation: Town MAINE County BROOMEStream Name LITTLE CHOCONUT CREEK

Tributary of \_\_\_\_\_

Latitude (N) 42° 11.0' Longitude (W) 75° 57.3'Type of Dam EARTH EMBANKMENTHazard Category CDate(s) of Inspection JULY 10, 1981Weather Conditions PARTLY CLOUDY - 85°Reservoir Level at Time of Inspection AT INTAKE RISER WEIR CRESTb. Inspection Personnel R. BARRON, L. BRANAGAN, W. CHECCHI, G. PAGE (SCS),  
P. SCERENTINO (BROOME COUNTY), S. PIERCE, C. SWEETc. Persons Contacted (Including Address & Phone No.) MR. DARRELL STONE -  
DEPUTY COMMISSIONER OF PUBLIC WORKS, BROOME COUNTY OFFICE BLDG.  
HOLLY ST., BINGHAMPTON, N.Y., 13901 - 607-772-2871  
MR. GARY PAGE - SCS BROOME COUNTY AIRPORT OFFICE  
- 607-773-2751

## d. History:

Date Constructed 1968 COMPLETED Date(s) Reconstructed \_\_\_\_\_Designer SOIL CONSERVATION SERVICE (N.Y.S. D.O.T.)Constructed By LES STRONG, INC.Owner BROOME COUNTY

2) Embankment

## a. Characteristics

- (1) Embankment Material COMPACTED TILL
- (2) Cutoff Type COMPACTED EARTH
- (3) Impervious Core NONE
- (4) Internal Drainage System YES
- (5) Miscellaneous CROWN VETCH AS EARTH COVER

## b. Crest

- (1) Vertical Alignment GOOD
- (2) Horizontal Alignment CURVED
- (3) Surface Cracks NONE
- (4) Miscellaneous TIRE TRACKS ALONG CREST

## c. Upstream Slope

- (1) Slope (Estimate) (V:H) 1 ON 3
- (2) Undesirable Growth or Debris, Animal Burrows 3-FOOT HIGH CROWN VETCH
- (3) Sloughing, Subsidence or Depressions MINOR EROSION ALONG AUXILIARY SPILLWAY EMBANKMENT CONTACT - TIRE TRACKS WEST OF INTAKE RISER

(4) Slope Protection CROWN VETCH ON SLOPES - SMALL STONE  
RIPRAP ON 10-FOOT BERM

(5) Surface Cracks or Movement at Toe NONE

d. Downstream Slope

(1) Slope (Estimate - V:H) 1 ON 2.5

(2) Undesirable Growth or Debris, Animal Burrows 3-FOOT HIGH CROWN  
VETCH

(3) Sloughing, Subsidence or Depressions MINOR EROSION ALONG  
WEST ABUTMENT CONTACT - FOOT PATH ON SLOPE  
WEST OF IMPACT BASIN

(4) Surface Cracks or Movement at Toe NONE

(5) Seepage NONE

(6) External Drainage System (Ditches, Trenches; Blanket) NONE

(7) Condition Around Outlet Structure GOOD - 3-FOOT HIGH CROWN  
VETCH - RIPRAP

(8) Seepage Beyond Toe NONE

e. Abutments - Embankment Contact

EARTH TO EARTH



(1) Erosion at Contact MINOR

(2) Seepage Along Contact NONE

3) Drainage System

a. Description of System TWO - 10-INCH DIAMETER - PERFORATED  
CORRUGATED METAL PIPES WITH SMALL ANIMAL GUARDS

b. Condition of System OKAY - WESTERLY ANIMAL GUARD  
VANDALIZED

c. Discharge from Drainage System NONE

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs,  
Piezometers, Etc.) NONE

93-15-3(9/80)

5) Reservoir

- a. Slopes STEEP WITH BRUSH AND TREES
- b. Sedimentation MINOR - FROM ACCESS ROADWAY AREA  
NORTH WEST OF DAM EMBANKMENT
- c. Unusual Conditions Which Affect Dam NONE

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) VILLAGE OF  
NEW IRELAND
- b. Seepage, Unusual Growth NONE
- c. Evidence of Movement Beyond Toe of Dam NONE
- d. Condition of Downstream Channel HEAVY BRUSH AND TREES  
ALONG CHANNEL

7) Spillway(s) (Including Discharge Conveyance Channel)

- a. General CONCRETE INTAKE RISER → CONCRETE CONDUIT → CONCRETE  
IMPACT BASIN WITH BAFFLE

AUXILIARY SPILLWAY - CHANNEL IN EARTH CUT-CROWN VETCH

- b. Condition of Service Spillway SATISFACTORY - MINOR RUSTING OF GALVANIZED  
TRASH RACKS, GRATING, AND HOLD DOWN BOLTS ; ONE SECTION OF GRATING  
MISSING ; MINOR EROSION OF CONCRETE ALONG WEIR CREST OF RISER ;  
VERTICAL CRACK RUNNING FULL HEIGHT OF THE OVERHANGING  
WING OF THE CONCRETE INTAKE RISER

c. Condition of Auxiliary Spillway SATISFACTORY - 3-FOOT HIGH CROWN VETCH  
ON SPILLWAY AND EMBANKMENTS; CATTAILS AND WET AREAS ALONG  
TOE OF EAST ABUTMENT; RUNOFF GULLIES ALONG  
BERM ON ABUTMENT SLOPE

d. Condition of Discharge Conveyance Channel HEAVY BRUSH AND  
TREES ALONG DOWNSTREAM CHANNEL

8) Reservoir Drain/Outlet

Type: Pipe ☒ Conduit \_\_\_\_\_ Other \_\_\_\_\_

Material: Concrete \_\_\_\_\_ Metal ☒ Other \_\_\_\_\_

Size: 12-INCH Length 46-FEET

Invert Elevations: Entrance 1185.0 Exit 1182.5

Physical Condition (Describe): \_\_\_\_\_ Unobservable ☒

Material: \_\_\_\_\_

Joints: \_\_\_\_\_ Alignment \_\_\_\_\_

Structural Integrity: \_\_\_\_\_

Hydraulic Capability: \_\_\_\_\_

Means of Control: Gate ☒ Valve \_\_\_\_\_ Uncontrolled \_\_\_\_\_

Operation: Operable ☒ Inoperable \_\_\_\_\_ Other \_\_\_\_\_

Present Condition (Describe): MINOR RUSTING OF SLIDE GATE  
STEM AND WRENCH SOCKET

9) Structural

- a. Concrete Surfaces SATISFACTORY - MINOR EROSION ALONG INTAKE  
RISER WEIR CREST, MINOR STAINING OF CONCRETE 0.5'  
ABOVE DISCHARGE INVERT AT IMPACT BASIN
- b. Structural Cracking MINIMAL - ONE VERTICAL CRACK ALONG  
THE HEIGHT OF THE OVERHANGING WING OF THE  
NORTH INTAKE RISER WALL AT THE CONTACT
- c. Movement - Horizontal & Vertical Alignment (Settlement) NONE
- d. Junctions with Abutments or Embankments GOOD
- e. Drains - Foundation, Joint, Face GOOD
- f. Water Passages, Conduits, Sluices GOOD
- g. Seepage or Leakage NONE

- h. Joints - Construction, etc. GOOD
- i. Foundation OKAY
- j. Abutments OKAY
- k. Control Gates NOT OBSERVABLE
- l. Approach & Outlet Channels APPROACH - NOT OBSERVABLE  
OUTLET - OKAY, SMALL STONE RIPRAP
- m. Energy Dissipators (Plunge Pool, etc.) BAFFLE IN IMPACT BASIN
- n. Intake Structures GOOD
- o. Stability
- p. Miscellaneous

10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)a. Description and Condition NONE

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

11) Operation Procedures (Lake Level Regulation):N/A (FLOOD CONTROL)

---

---

---

---

---

---

---

---

---

APPENDIX C

HYDROLOGIC/HYDRAULIC  
ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation (ft.)</u>	<u>Surface Area (acres)</u>	<u>Storage Capacity (acre-ft.)</u>
1) Top of Dam	<u>1241.0</u>	<u>62.8</u>	<u>1271</u>
2) Design High Water (Max. Design Pool)	<u>1234.0</u>	<u>51.8</u>	<u>873</u>
3) Auxiliary Spillway Crest	<u>1231.1</u>	<u>47.3</u>	<u>733</u>
4) Pool Level with Flashboards	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
5) Service Spillway Crest	<u>1199.8</u>	<u>5.7</u>	<u>0</u>

DISCHARGES

	<u>Volume (cfs)</u>
1) Average Daily	<u>UNKNOWN</u>
2) Spillway @ Maximum High Water	<u>15685</u>
3) Spillway @ Design High Water	<u>1950</u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>132</u>
5) Low Level Outlet	<u>14</u>
6) Total (of all facilities) @ Maximum High Water	<u>          </u>
7) Maximum Known Flood	<u>UNKNOWN</u>
8) At Time of Inspection	<u>± .01</u>



CREST:

ELEVATION: 1241.0Type: GRASSED EARTHWidth: 19' Length: 590'Spillover AUXILIARY CHANNELLocation EAST END OF DAM

SPILLWAY:

SERVICE

1199.8

Elevation

AUXILIARY

1231.1R/C DROP INLET

Type

EARTH CUT CHANNELWEIR LENGTH 13.3'

Width

160'Type of Control

✓

Uncontrolled

✓

Controlled:Type(Flashboards; gate)NumberSize/LengthInvert MaterialAnticipated Length  
of operating serviceChute LengthHeight Between Spillway Crest  
& Approach Channel Invert  
(Weir Flow)

## HYDROMETEROLOGICAL GAGES:

Type : NONE

Location: \_\_\_\_\_

Records:

Date - \_\_\_\_\_

Max. Reading - \_\_\_\_\_

## FLOOD WATER CONTROL SYSTEM:

Warning System: CONTACT COUNTY CIVIL DEFENSE — COUNTY  
CURRENTLY WORKING ON NOTIFICATION PROGRAM FOR RESIDENTS

Method of Controlled Releases (mechanisms):

RESERVOIR DRAIN  
\_\_\_\_\_  
\_\_\_\_\_

DRAINAGE AREA: 3.49 SQ. Mi.

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: FARMS WOODLANDS

Terrain - Relief: GRASS - FORESTS

Surface - Soil: TILL

Runoff Potential (existing or planned extensive alterations to existing  
(surface or subsurface conditions)

NONE

Potential Sedimentation problem areas (natural or man-made; present or future)

ACCESS ROADWAY NORTHWEST OF DAM

EMBANKMENT

Potential Backwater problem areas for levels at maximum storage capacity  
including surcharge storage:

NONE

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the  
Reservoir perimeter:

Location: NONE

Elevation: \_\_\_\_\_

Reservoir:

Length @ Maximum Pool \_\_\_\_\_ (Miles)

Length of Shoreline (@ Spillway Crest) 0.5 (Miles)

Project NY C&E Dam Inspection Acct. No. 7594 Page 1 of 2  
 Subject Little Chocoma Comptd. By \_\_\_\_\_ Date 8/20/81  
 Detail \_\_\_\_\_ Ch'd. By \_\_\_\_\_ Date \_\_\_\_\_

DRAINAGE AREA = 3.49 sq mi

Impervious areas include:

2 ponds	9.0 acres
reservoir	5.7 acres
total	14.7 acres

The ratio of impervious area to total area is:

$$\frac{14.7 \text{ ac}}{3.5 \text{ sq mi}} = 0.007$$

#### WATERSHED PARAMETERS

Snyder Unit Hydrograph  
 Lag time:

$$t_p = C_L (LLC)^{0.3}$$

Where  $C_L = 2.0$   
 $L = 3.6 \text{ mi}$   
 $L_c = 1.8 \text{ mi}$

$$t_p = 2.0 (3.6 \cdot 1.8)^{0.3} = 3.50 \text{ hrs}$$

Unit rainfall duration

$$t_r = t_p / 5.5$$

$$= 3.50 / 5.5 = 0.64 \text{ hrs}$$

adjusted  $t_r = 0.5 \text{ hrs}$

Adjusted Lag time

$$t_{pe} = t_p + 0.25 (t_a - t_r)$$

$$= 3.5 + 0.25 (0.5 - 0.64) = 3.47 \text{ hrs.}$$

Peaking Coefficient,  $C_P = 0.6$

### Base Flow

Based on design computations for the dam, the base flow for the stream is 47 cfs.  
 (These design computations are included after sheet C-2.)

Based on other dam inspection reports,  $R_{TOR} = 1.5$   
 and  $QR_{CSN}$  is 15%


### Storage

Stage-storage values were obtained from the design computations and are included following sheet 2

### Spillway Capacity

Spillway capacity computations were obtained from the design computations and are included following sheet 2

### Low Level Outlet



Calculate discharge:

$$\begin{aligned}
 Q &= 0.6 A \sqrt{2gH} \\
 &= 0.6 \pi (.5)^2 \sqrt{2(32.2)(1199.8 - 1185.5)} \\
 &= 14.3 \text{ cfs}
 \end{aligned}$$

STATE New York PROJECT Little Chocanet Creek Watershed Site 2C  
 BY JCI DATE 9/65 CHECKED BY J. H. H. H. DATE 10/65 JOB NO. NY-2018 ✓  
 SUBJECT Principal Spillway SHEET 2 OF 3

Site	100-year frequency									
	1-day rainfall			10-day rainfall			Q <sub>10</sub>	T <sub>c</sub>	RA	Serial No.
	CN AMCII	Rainfall	Runoff Q <sub>1</sub>	CN AMCII	Rainfall	Runoff Q <sub>10</sub>				
2A	83	5.8	3.90	69	9.7	5.82	0.670	0.50	763	6
2B	74	5.8	3.02	57	9.7	4.26	0.709	1.36	160	6
2C	77	5.8	3.30	61	9.7	4.79	0.689	1.44	349	6
2E	73	5.8	2.92	56	9.7	4.13	0.707	2.41	102	14
2	74	5.8	3.02	57	9.7	4.26	0.709	1.34	50	6

Compute the climatic index

$$C_i = \frac{100 P_0}{(T_0)^2} = \frac{100 \times 36.24}{45.8^2} = 1.73 \quad \begin{matrix} P_0 = 36.24 \\ T_0 = 45.8 \end{matrix}$$

Channel Losses

The climatic index is greater than (1)

The soils would reduce the loss to a min.

∴ channel losses are not considered.

Base Flow (Determine the minimum permissible base flow)

Assume 2 csm base flow

From Table 2.4 using  $C_i = 1.73$  Base Flow = 0.225 csm  
 = 7.69 csm

Snowmelt (Determine the minimum permissible snow melt)

$$S_{mc} = \frac{P_m (40 - T_m)}{2} \quad \begin{matrix} T_m = 31.3 \\ P_m = 2.82 \end{matrix}$$

$$= \frac{2.82 (40 - 31.3)}{2} = 12.57 \text{ csm}$$

$$S_{mi} = \frac{2.82 (40 - 31.3)}{53.8} = 0.462 \text{ csm}$$

This rate is greater than the computed base flow  
 ∴ snow melt will be used.

STATE <i>New York</i>	PROJECT <i>Little Chocoma</i>	SITE <i>2-C</i> ✓	
BY <i>LPH</i>	DATE <i>10/65</i>	CHECKED BY <i>WY</i>	DATE <i>11/65</i>
SUBJECT <i>Principal Spillway</i>		JOB NO. <i>NY-2018</i>	
		SHEET <i>2 OF 4</i>	

$Q_{10} = 4.79$  Snowmelt =  $0.500$ /day, Table 2.10  
 $A = 3.49$  sq mi.  $A Q_{10} = 16.717$  mi<sup>2</sup> inches Serial #6

Time	Preliminary PSMC	Accum. Snow Melt	PSMC	PSMC	Preliminary PSH	Snow melt	PSH
days	Inches	Inches	Inches	Acft	cfs	cfs	cfs
0	0	0	0	0	0	47	47
0.1	0.003	0.050	0.053	10	6		53
0.5	0.033	0.250	0.283	53	8		55
1.0	0.079	0.500	0.579	108	9		56
2.0	0.179	1.000	1.179	219	15		58
3.0	0.313	1.500	1.813	338	14		61
3.5	0.404	1.750	2.154	401	19		66
4.0	0.525	2.000	2.525	470	24		71
4.2	0.585	2.100	2.685	500	34		81
4.4	0.671	2.200	2.871	534	48		95
4.6	0.776	2.300	3.076	573	57		104
4.7	0.842	2.350	3.192	594	70		117
4.8	0.925	2.400	3.325	616	94		141
4.9	1.051	2.450	3.501	652	152		199
5.0	2.071	2.500	4.571	851	1835		1882
5.1	3.327	2.580	5.877	1094	614		661
5.2	3.753	2.600	6.353	1183	218		265
5.3	3.920	2.650	6.570	1223	106		153
5.4	4.010	2.700	6.710	1249	71		118
5.5	4.075	2.750	6.825	1271	56		103
5.6	4.126	2.800	6.926	1289	43		90
5.8	4.201	2.900	7.101	1322	33		80
6.0	4.262	3.000	7.262	1352	27		74
6.5	4.384	3.250	7.634	1421	23		70
7.0	4.476	3.500	7.976	1485	17		64
8.0	4.611	4.000	8.611	1603	12		59
9.0	4.713	4.500	9.213	1715	9		65
10.0	4.785	5.000	9.785	1822	7		54
10.1	4.790	5.050	9.840	1832	0.3		47
10.3	4.790	5.150	9.940	1850	0		47
11.0	4.790	5.500	10.290	1915			

# Little Choconut Watershed

Site 2-C NY-2018

3-1

## Stage Storage Computations

Area in Sq in = Planimeter Reading x 0.003827


Map Scale: 1" = 100'

1 sq in = 0.2296 Acres

Elev	Planimeter Reading	Area Acres	E Area Acres	Avg Area Acres	Diff. in Elev.	Vol Ac FT	Accum. Vol Ac FT	Accum. Vol. Minus Sediment
1184.0	0	.03					0	
			.03	.02	1.0	.02		
1185.0	38	.03					.02	
			1.14	.57	5.0	2.85		
1190.0	1256	1.11					2.87	
			4.17	<del>2.08</del> 2.04	5.0	<del>10.40</del> 10.20		
1195.0	3482	3.06					13.07	
			8.93	4.47	5.0	22.35		
1200.0	6662	5.87	Crest of Riser to EL 1199.8			1199.8	35.42	0
			16.90	8.45	5.0	42.25	62	1.28
1205.0	12,532	11.03					77.87	35.01
			27.99	13.95	5.0	69.75		
1210.0	19,272	16.96					147.42	96.23
			41.07	20.54	5.0	102.70	62	
1215.0	27,386	24.11					250.32	190.41
			54.78	27.39	5.0	136.95		
1220.0	34,848	30.67					387.27	318.84
			68.27	34.14	5.0	170.70	27	
1225.0	42,717	37.60					557.97	481.03
			83.39	41.69	5.0	208.45		
1230.0	52,026	45.79					766.22	680.96
			98.84	49.42	5.0	247.10	42	
1235.0	60,266	53.05					1013.32	919.52
			119.27	57.14	5.0	285.70	52	
1240.0	69,553	61.22					1299.02	1205.22
			131.19	65.59	5.0	327.95	22	
1245.0	79,498	69.97					1627.17	1533.17
			149.89	74.95	5.0	374.75	4626.47	
1250.0	90,801	79.92					2001.92	1907.72

4618/19/65





STATE NEW YORK PROJECT LITTLE CHOCOMUT SITE 2 C  
 BY J. H. H. H. DATE 11/65 CHECKED BY LCI DATE 11/65 JOB NO. NY-2018  
 SUBJECT Flow Constants SHEET 4 OF 1

Use a 30" pipe

Weir Flow Over Crest of Riser

$$Q = C L H^{3/2}$$

$$Q = (3.1) (730) H^{3/2}$$

$$C = 3.1$$

Center wall

$$L = 3D \times 2 = 15.0' - 2.0' = 13.0$$

Refer to ES-151

$$Q = 40.3 H^{3/2}$$

Pipe Flow For 30" pipe

$$Q = CA \sqrt{2gh}$$

$$Q = 0.49 \times 4.91 \times 8.02^{1/2}$$

$$Q = 19.30 h^{1/2}$$

$$C = \frac{1}{\sqrt{2 + K_p + L_p}}$$

$$C = \frac{1}{\sqrt{2 + 0.0786 \times 272}}$$

$$C = \frac{1}{\sqrt{2 + 2.14}}$$

$$C = \frac{1}{2.04} = 0.49$$

$$A_p = 4.91$$

$$L_p = 272$$


$$n = 0.012$$

$$K_p = 0.0786$$

STATE New York PROJECT Little Choconut Creek W.S. S.T. 2.C  
BY JFH DATE 3/66 CHECKED BY LCI DATE 3/66 JOB NO. NY-2018  
SUBJECT 1/2 Yr Hp Computations (Emergency Spillway) SHEET 4 OF 2

$$n = 0.040$$

EMERGENCY SPILLWAY $L = 240'$ $b = 160'$					
Q/b	dx	$\sqrt{y/2g}$	$S_o(L-50)$	Hp	Q
2	4.89	0.00	3.80	1.09	320
4	5.42	0.01		1.63	640
6	5.83	0.02		2.05	960
8	6.20	0.02		2.42	1280
10	6.57	0.03		2.80	1600
15	7.45	0.05		3.51	2400
20	7.79	0.08		4.07	3200
25	8.28	0.11		4.59	4000
30	8.81	0.13		5.14	4800
35	9.24	0.16		5.60	5600
40	9.73	0.18		6.11	6400
50	10.43	0.24		6.87	8000
60	11.12	0.31		7.63	9600
70	11.78	0.35		8.33	11,200
80	12.38	0.42		9.00	12800
90	12.89	0.48		9.57	14400
100	13.44	0.54		10.18	16000
120	14.48	0.64		11.32	19200
140	15.43	0.76		12.39	22400
160	16.36	0.83		13.39	25600
180	17.24	0.94		14.38	28800
200	18.05	1.02	3.80	15.27	32000




LITTLE CHOCONUT CREEK W/S 2/10/61 3/10/61

Site No. 11-2018  
 EMERGENCY 600-187 DISCHARGE  
 H<sub>2</sub>O CURVE

3/10/61  
 3/10/61  
 ✓

K-E SEMI-LOGARITHMIC 46 5493  
 5 CYCLES 7 10 DIVISIONS MADE IN U.S.A.  
 KNUFFEL & ESSER CO.



LITTLE CHOCONUT CREEK WATERSHED

SITE 2-C

NY-2018

STAGE DISCHARGE COMPUTATIONS

ELEV.	WEIR @ RISER		FLOW CREST	PIPE FLOW			EMERGENCY SPILLWAY FLOW		Q TOTAL
	1/ H	3/2 H		2/ h	1/2 h	19.30 h <sup>1/2</sup>	Hp	Q	
Riser Crest									
1199.8	0	0	0						0
1200.3	.5	.35	14.1						14
1200.8	1.0	1.0	40.3	16.3	4.04	78			40
1201.4	1.6	2.02	81.4	16.9	4.11	79			79
1201.8	2.0	2.83	114	17.3	4.16	80			80
1203.0				18.5	4.30	83			83
1206.0				21.5	4.64	90			90
1210.0				25.5	5.05	97			97
1215.0				30.5	5.52	107			107
1220.0				35.5	5.96	115			115
1225.0				40.5	6.36	123			123
Crest of Emergency									
1231.1				46.6	6.83	132	0	0	132
1232.2				47.7	6.91	133	1.1	320	453
1233.1				48.6	6.97	135	2.0	918	1053
1234.1				49.6	7.04	136	3.0	1850	1986
1235.0				50.5	7.11	137	3.9	3000	3137
1236.1				51.6	7.18	139	5.0	4580	4719
1237.5				53.0	7.28	141	6.4	6400	7041
1238.7				54.2	7.36	142	7.6	8500	8642
1240.0				55.5	7.45	144	8.9	12700	12844
<del>1242.1</del>				<del>56.6</del>	<del>7.52</del>	<del>145</del>	<del>10.0</del>	<del>15500</del>	<del>15643</del>
1242.5				58.0	7.62	147	11.4	19800	19947
1243.7				59.2	7.69	148	12.6	23200	23348
1245.0				60.5	7.78	150	13.9	27000	27150
1247	1/	Riser Crest	@Elev. 1199.8			153		33200	33350
	2/	Invert of Pipe	@Elev. 1180.0	@ Pipe	@Elev. 1181.25				
		Assume Head Loss of	3.25 thru biff.						
		Consider	Water Surface @Elev. 1184.5						

STATE	New York		PROJECT	Little Chocanut Creek W.S. Site 2C	
BY	LCI	DATE	CHECKED BY	DATE	JOB NO.
SUBJECT	Exit Channel Slope and Velocity (Em. Spill.)			NY-2018	
			SHEET 4 OF 5		
<u>Exit Channel Slope - Veg. Earth</u>					

$$Q_{total} = 1950 \text{ cfs}$$

$$Q_{pipe} = 136 \text{ cfs}$$

$$Q_{em} = Q_{total} - Q_{pipe} = 1950 - 136 = 1814 \text{ cfs}$$

$$25\% \text{ } Q = 0.25 \frac{1814}{160} = 2.83 \text{ cfs}$$

$$S_c = 0.028 \quad (ES 98 3 of 4)$$

Velocity ( $V_c$ ) in exit channel

$$\frac{Q_{em}}{b} = \frac{1814}{160} = 11.3 \text{ cfs}$$

$$V_c = 7.8 \text{ fps} < (7.5 \text{ fps} + 25\%) \therefore \text{OK}$$

$V_c$  selected from  
Part 6 - V.D. Method  
of Reservoir Flood  
Routing

[illegible]

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT  
ROUTE HYDROGRAPH TO  
END OF NETWORK

1

1



\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HSC-1)  
 DAN SAFETY VERSION JULY 1978  
 LAST MODIFICATION 25 SEP 78  
 \*\*\*\*\*

RUN DATE: 24 AUG 1981

NEW YORK C. OF E. PHASE 1 DAM INSPECTION  
 LITTLE CHOCHUT DAM SITE 2-C  
 FULL AND HALF PMF FLOOD ANALYSIS

JOB SPECIFICATION										
NO	NR	NRH	NRH	IOAY	INR	ININ	NETBC	IPLT	IPRT	INSTAN
100	0	30	0	0	0	0	0	0	0	0
JOPER				5	0	0	0	0	0	0
JOPER				5	0	0	0	0	0	0

MULTI-PLAN ANALYSES TO BE PERFORMED  
 NPLAN= 1 RTIO= 2 LRTIO= 1

RTIOS= 0.50 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	IMANE	ISTAGE	IAUTO
1	0	0	0	2	0	1	0	0

HYDROGRAPH DATA

INHYD	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISANE	LOCAL
1	1	3.50	0.0	3.50	0.0	0.0	0	1	0

PRECIP DATA

SPFE	PHS	R6	R12	R24	R48	R72	R96
0.0	21.00	111.00	123.00	132.00	142.00	0.0	0.0

TRSPC COMPUTED BY THE PROGRAM IS 0.800

LOSS DATA

LROPT	STRES	DLTKR	RTIOL	ERAIN	STRES	RTIOK	STRTL	CHSTL	ALSHX	RTIMP
0	0.0	0.0	1.00	0.0	0.0	1.00	1.00	0.10	0.0	0.01

UNIT HYDROGRAPH DATA

TP= 3.47 CP=0.60 NTA= 0

RECESSION DATA

STRIO= 47.00 ORCSH= -0.15 RTIOR= 1.50  
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 7.80 AND R= 6.84 INTERVALS

UNIT HYDROGRAPH #1 END-OF-PERIOD ORDINATES, LAG= 3.49 HOURS, CP= 0.61 VOL= 1.00									
20.	74.	147.	231.	309.	367.	396.	390.	352.	304.
262.	227.	196.	169.	146.	126.	109.	94.	81.	70.
61.	52.	45.	39.	34.	29.	25.	22.	19.	16.

18.  
3.

12.

10.

9.

8.

7.

6.

5.

4.

4.

0		END-OF-PERIOD FLOW										COMP 0	
NO.DA	NR.NH	PERIOD	RAIN	EICS	LOSS	COMP 0	NO.DA	NR.NH	PERIOD	RAIN	EICS	LOSS	COMP 0
1.01	0.30	1	0.00	0.00	0.00	45.	1.02	1.30	51	0.05	0.00	0.05	38.
1.01	1.00	2	0.00	0.00	0.00	43.	1.02	2.00	52	0.05	0.00	0.05	33.
1.01	1.30	3	0.00	0.00	0.00	42.	1.02	2.30	53	0.05	0.00	0.05	30.
1.01	2.00	4	0.00	0.00	0.00	40.	1.02	3.00	54	0.05	0.00	0.05	26.
1.01	2.30	5	0.00	0.00	0.00	38.	1.02	3.30	55	0.05	0.00	0.05	24.
1.01	3.00	6	0.00	0.00	0.00	37.	1.02	4.00	56	0.05	0.00	0.05	22.
1.01	3.30	7	0.00	0.00	0.00	35.	1.02	4.30	57	0.05	0.00	0.05	21.
1.01	4.00	8	0.00	0.00	0.00	34.	1.02	5.00	58	0.05	0.00	0.05	21.
1.01	4.30	9	0.00	0.00	0.00	33.	1.02	5.30	59	0.05	0.00	0.05	20.
1.01	5.00	10	0.00	0.00	0.00	31.	1.02	6.00	60	0.05	0.00	0.05	19.
1.01	5.30	11	0.00	0.00	0.00	30.	1.02	6.30	61	0.17	0.12	0.05	18.
1.01	6.00	12	0.00	0.00	0.00	29.	1.02	7.00	62	0.17	0.12	0.05	24.
1.01	6.30	13	0.01	0.00	0.01	28.	1.02	7.30	63	0.17	0.12	0.05	40.
1.01	7.00	14	0.01	0.00	0.01	27.	1.02	8.00	64	0.17	0.12	0.05	66.
1.01	7.30	15	0.01	0.00	0.01	26.	1.02	8.30	65	0.17	0.12	0.05	102.
1.01	8.00	16	0.01	0.00	0.01	25.	1.02	9.00	66	0.17	0.12	0.05	145.
1.01	8.30	17	0.01	0.00	0.01	24.	1.02	9.30	67	0.17	0.12	0.05	191.
1.01	9.00	18	0.01	0.00	0.01	23.	1.02	10.00	68	0.17	0.12	0.05	236.
1.01	9.30	19	0.01	0.00	0.01	22.	1.02	10.30	69	0.17	0.12	0.05	277.
1.01	10.00	20	0.01	0.00	0.01	21.	1.02	11.00	70	0.17	0.12	0.05	312.
1.01	10.30	21	0.01	0.00	0.01	20.	1.02	11.30	71	0.17	0.12	0.05	343.
1.01	11.00	22	0.01	0.00	0.01	19.	1.02	12.00	72	0.17	0.12	0.05	369.
1.01	11.30	23	0.01	0.00	0.01	18.	1.02	12.30	73	0.93	0.88	0.05	407.
1.01	12.00	24	0.01	0.00	0.01	17.	1.02	13.00	74	0.93	0.88	0.05	442.
1.01	12.30	25	0.07	0.00	0.07	17.	1.02	13.30	75	1.12	1.07	0.05	616.
1.01	13.00	26	0.07	0.00	0.07	17.	1.02	14.00	76	1.12	1.07	0.05	820.
1.01	13.30	27	0.08	0.00	0.08	16.	1.02	14.30	77	1.40	1.35	0.05	1103.
1.01	14.00	28	0.08	0.00	0.08	16.	1.02	15.00	78	1.40	1.35	0.05	1458.
1.01	14.30	29	0.11	0.00	0.11	15.	1.02	15.30	79	1.70	1.65	0.05	1875.
1.01	15.00	30	0.11	0.00	0.11	15.	1.02	16.00	80	5.39	5.34	0.05	2410.
1.01	15.30	31	0.13	0.00	0.13	14.	1.02	16.30	81	1.31	1.26	0.05	3081.
1.01	16.00	32	0.41	0.23	0.18	19.	1.02	17.00	82	1.31	1.26	0.05	3807.
1.01	16.30	33	0.10	0.05	0.05	32.	1.02	17.30	83	1.03	0.98	0.05	4525.
1.01	17.00	34	0.10	0.05	0.05	52.	1.02	18.00	84	1.03	0.98	0.05	5158.
1.01	17.30	35	0.08	0.03	0.05	77.	1.02	18.30	85	0.08	0.03	0.05	5408.
1.01	18.00	36	0.08	0.03	0.05	104.	1.02	19.00	86	0.08	0.03	0.05	5814.
1.01	18.30	37	0.01	0.00	0.01	128.	1.02	19.30	87	0.08	0.03	0.05	5740.
1.01	19.00	38	0.01	0.00	0.01	146.	1.02	20.00	88	0.08	0.03	0.05	5406.
1.01	19.30	39	0.01	0.00	0.01	153.	1.02	20.30	89	0.08	0.03	0.05	4933.
1.01	20.00	40	0.01	0.00	0.01	148.	1.02	21.00	90	0.08	0.03	0.05	4416.
1.01	20.30	41	0.01	0.00	0.01	137.	1.02	21.30	91	0.08	0.03	0.05	3890.
1.01	21.00	42	0.01	0.00	0.01	123.	1.02	22.00	92	0.08	0.03	0.05	3389.
1.01	21.30	43	0.01	0.00	0.01	109.	1.02	22.30	93	0.08	0.03	0.05	2944.
1.01	22.00	44	0.01	0.00	0.01	96.	1.02	23.00	94	0.08	0.03	0.05	2559.
1.01	22.30	45	0.01	0.00	0.01	83.	1.02	23.30	95	0.08	0.03	0.05	2226.
1.01	23.00	46	0.01	0.00	0.01	73.	1.03	0.00	96	0.08	0.03	0.05	1939.
1.01	23.30	47	0.01	0.00	0.01	64.	1.03	0.30	97	0.0	0.0	0.0	1690.
1.02	0.0	48	0.01	0.00	0.01	56.	1.03	1.00	98	0.0	0.0	0.0	1474.
1.02	0.30	49	0.05	0.00	0.05	49.	1.03	1.30	99	0.0	0.0	0.0	1285.
1.02	1.00	50	0.05	0.00	0.05	43.	1.03	2.00	100	0.0	0.0	0.0	1119.

SUN 23.86 20.18 3.67 85063.  
( 606. )( 513. )( 93. )( 2408.72 )

PEAK 5814.  
CFS 165.  
6-HOUR 4641.  
24-HOUR 1707.  
72-HOUR 845.  
TOTAL VOLUME 84480.  
2392.

INCHES  
MM  
AC-FT

12.34  
313.34  
2302.

18.15  
460.96  
3386.

18.71  
475.26  
3491.

18.71  
475.26  
3491.

THOUS CU H

2839.

4176.

4306.

4306.

**STATION 1**[illegible]



[illegible]



•OVER•

# 1 FOR PLAN 1, RTIO 1

## HYDROGRAPH AT STA

23.	22.	21.	20.	19.	18.	17.	16.
15.	14.	13.	12.	11.	10.	9.	8.
7.	6.	5.	4.	3.	2.	1.	0.
68.	62.	55.	48.	42.	36.	32.	28.
19.	17.	15.	13.	12.	11.	10.	9.
9.	12.	20.	33.	51.	72.	95.	118.
171.	185.	203.	241.	308.	410.	551.	729.
1541.	1903.	2262.	2579.	2804.	2907.	2870.	2703.
1945.	1695.	1472.	1279.	1113.	970.	845.	737.

## TOTAL VOLUME

PEAK	6-HOUR	24-HOUR	72-HOUR
2907.	2321.	854.	422.
82.	66.	24.	12.
CFS	6.17	9.07	9.36
INCHES	156.67	230.46	237.63
MM	1151.	1693.	1745.
AC-FT	1419.	2088.	2153.
THOUS CU M			

# 1 FOR PLAN 1, RTIO 2

## HYDROGRAPH AT STA

45.	43.	42.	40.	38.	37.	35.	34.
30.	29.	28.	27.	26.	25.	24.	23.
20.	20.	19.	18.	17.	17.	16.	15.
14.	19.	32.	52.	77.	104.	128.	146.
137.	123.	109.	96.	83.	73.	64.	56.
38.	33.	30.	26.	24.	22.	21.	21.
18.	24.	40.	66.	102.	145.	191.	236.
343.	369.	407.	482.	616.	820.	1103.	1458.
3081.	3807.	4525.	5158.	5608.	5814.	5740.	5406.
3890.	3389.	2944.	2559.	2226.	1939.	1690.	1474.

## TOTAL VOLUME

PEAK	6-HOUR	24-HOUR	72-HOUR
5814.	4641.	1707.	845.
165.	131.	48.	24.
CFS	12.34	18.15	18.71
INCHES	313.34	460.96	475.26
MM	2302.	3386.	3491.
AC-FT	2839.	4176.	4306.
THOUS CU M			

## HYDROGRAPH ROUTING

### ROUTED HYDROGRAPH AT DAM NO BREACH

ISTAO	ICORP	IECON	ITAPE	JPLT	JPRT	INAME	ISTACE	IAUTO
1	1	0	0	0	0	1	0	0
QLOSS	CLOSS	AVC	IRCS	ISAME	IOPT	IPNP	LISTR	
0.0	0.0	0.0	1	1	0	0	0	

WSTPS WSTD LAG ANSK X TSK STORA ISPRAT  
20 0 0 0.0 0.0 -1200. -1

STAGE 1199.80 1231.10 1233.10 1235.00 1237.50 1238.70 1240.00 1242.50 1245.00 1247.00  
 FLOW 0.0 132.00 1053.00 3137.00 7041.00 9642.00 12844.00 19947.00 27150.80 33350.00

CAPACITY= 0. 96. 319. 681. 1205. 1533.

ELEVATION= 1200. 1210. 1220. 1230. 1240. 1245.

CREL SPWID COQH EXPN ELEV COOL CARZA EXPL  
 1199.6 0.0 0.0 0.0 0.0 0.0 0.0 0.0

DAN DATA  
 TOPEL COOD EXPD DANWID  
 1241.0 2.7 1.5 600.

STATION 1, PLAN 1, RATIO 1

# END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW									
0.	1.	2.	3.	4.	5.	6.	7.	8.	9.
3.	4.	5.	6.	7.	8.	9.	10.	11.	12.
5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
13.	14.	15.	16.	17.	18.	19.	20.	21.	22.
17.	18.	19.	20.	21.	22.	23.	24.	25.	26.
16.	17.	18.	19.	20.	21.	22.	23.	24.	25.
27.	28.	29.	30.	31.	32.	33.	34.	35.	36.
77.	78.	79.	80.	81.	82.	83.	84.	85.	86.
2182.	1963.	1734.	1518.	1324.	1153.	1028.	956.	874.	790.

STORAGE									
1.	2.	3.	4.	5.	6.	7.	8.	9.	10.
8.	9.	10.	11.	12.	13.	14.	15.	16.	17.
11.	12.	13.	14.	15.	16.	17.	18.	19.	20.
12.	13.	14.	15.	16.	17.	18.	19.	20.	21.
28.	31.	32.	33.	34.	35.	36.	37.	38.	39.
38.	39.	40.	41.	42.	43.	44.	45.	46.	47.
36.	37.	38.	39.	40.	41.	42.	43.	44.	45.
61.	62.	63.	64.	65.	66.	67.	68.	69.	70.
274.	342.	424.	520.	626.	739.	835.	889.	906.	905.
897.	887.	876.	866.	856.	846.	832.	814.	790.	766.

STAGE									
1199.9	1200.0	1200.1	1200.2	1200.3	1200.4	1200.5	1200.6	1200.7	1200.8
1200.6	1200.7	1200.8	1200.9	1201.0	1201.1	1201.2	1201.3	1201.4	1201.5
1201.0	1201.1	1201.2	1201.3	1201.4	1201.5	1201.6	1201.7	1201.8	1201.9
1201.1	1201.2	1201.3	1201.4	1201.5	1201.6	1201.7	1201.8	1201.9	1202.0
1202.8	1203.0	1203.2	1203.4	1203.6	1203.8	1204.0	1204.2	1204.4	1204.6
1203.8	1203.8	1203.8	1203.8	1203.8	1203.8	1203.8	1203.8	1203.8	1203.8
1203.6	1203.6	1203.6	1203.6	1203.6	1203.6	1203.6	1203.6	1203.6	1203.6
1206.3	1206.9	1207.6	1208.5	1209.5	1210.4	1211.2	1212.3	1213.7	1215.6
1218.0	1220.6	1222.9	1225.6	1228.5	1231.1	1233.2	1235.0	1236.3	1237.5
1234.1	1233.9	1233.7	1233.5	1233.3	1233.2	1233.0	1232.9	1232.7	1232.5

PEAK OUTFLOW IS 2354. AT TIME 44.50 HOURS

CFS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
2354.	1624.	463.	226.	22575.	

CBS  
INCHES  
HI

67.

46.  
4.32  
109.63

13.  
4.92  
124.91

6.  
5.00  
127.00

639.  
5.00  
127.00

AC-FT  
THOUS CU H

805.  
993.

918.  
1132.

933.  
1151.

933.  
1151.

STATION 1, PLAN 1, RATIO 2  
END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW											
1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.
7.	10.	10.	11.	11.	11.	11.	11.	11.	11.	11.	11.
10.	11.	12.	13.	14.	16.	18.	21.	23.	25.	27.	29.
25.	27.	30.	31.	32.	33.	33.	33.	33.	33.	33.	33.
34.	34.	34.	34.	35.	38.	41.	44.	46.	48.	50.	53.
32.	32.	33.	34.	35.	38.	41.	44.	46.	48.	50.	53.
48.	50.	56.	60.	65.	72.	81.	90.	100.	113.	128.	148.
4311.	3799.	3317.	2809.	2291.	2003.	1749.	1526.	1331.	1151.	933.	716.

STORAGE

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.
15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.
22.	23.	23.	23.	24.	24.	24.	24.	24.	24.	24.	24.
25.	25.	26.	27.	29.	32.	36.	41.	47.	52.	57.	61.
57.	61.	65.	68.	70.	72.	74.	75.	75.	74.	73.	72.
76.	76.	76.	73.	75.	79.	84.	88.	91.	91.	88.	84.
72.	72.	72.	73.	75.	79.	84.	88.	91.	91.	88.	84.
122.	135.	149.	165.	185.	212.	249.	299.	364.	449.	556.	687.
558.	695.	843.	951.	1002.	1026.	1030.	1026.	1015.	999.	956.	887.
982.	965.	949.	933.	918.	903.	889.	877.	866.	857.	848.	839.

STAGE

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.
1200.0	1200.2	1200.4	1200.5	1200.7	1200.8	1200.9	1201.0	1201.1	1201.2	1201.3	1201.4
1201.4	1201.5	1201.6	1201.7	1201.8	1201.9	1202.0	1202.1	1202.2	1202.3	1202.4	1202.5
1202.2	1202.2	1202.2	1202.3	1202.3	1202.3	1202.4	1202.4	1202.4	1202.4	1202.4	1202.4
1202.4	1202.5	1202.5	1202.7	1202.9	1203.2	1203.7	1204.2	1204.8	1205.3	1205.8	1206.3
1205.8	1206.3	1206.7	1207.0	1207.3	1207.5	1207.6	1207.7	1207.7	1207.8	1207.9	1208.0
1207.9	1207.9	1207.9	1207.9	1207.8	1207.8	1207.7	1207.7	1207.6	1207.6	1207.6	1207.6
1207.5	1207.4	1207.4	1207.5	1207.8	1208.1	1208.7	1209.5	1210.2	1210.6	1211.2	1211.8
1211.2	1211.7	1212.4	1213.1	1214.0	1215.2	1216.9	1219.1	1221.2	1223.6	1226.1	1228.6
1226.6	1230.3	1233.1	1235.2	1236.1	1236.5	1236.7	1236.6	1236.4	1236.1	1235.8	1235.5
1235.8	1235.4	1235.1	1234.8	1234.5	1234.2	1234.0	1233.7	1233.5	1233.4	1233.3	1233.2

PEAK OUTFLOW IS 5716. AT TIME 43.50 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
5716.	4304.	1314.	638.	63792.
162.	122.	37.	18.	1806.
CFS	11.44	13.96	14.13	14.13
INCHES	290.58	354.70	358.88	358.88
MM	2134.	2605.	2636.	2636.
AC-FT	2633.	3214.	3252.	3252.
THOUS CU H				

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO 1	RATIO 2
				0.50	1.00

HYDROGRAPH AT	1	3.50	1	2907.	5014.
	(	9.07)	(	82.32)	( 164.63)

ROUTED TO	1	3.50	1	2354.	5716.
	(	9.07)	(	66.67)	( 161.85)

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....

ELEVATION  
STORAGE  
OUTFLOW

INITIAL VALUE  
1199.80  
0.  
0.

SPILLWAY CHEST TOP OF DAM  
1199.80 1241.00  
0. 1271.  
0. 15685.

RATIO  
OF  
PHF

MAXIMUM  
RESERVOIR  
W.S.ELEV

MAXIMUM  
DEPTH  
OVER DAM

MAXIMUM  
STORAGE  
AC-FT

MAXIMUM  
OUTFLOW  
CFS

DURATION  
OVER TOP  
HOURS

TIME OF  
MAX OUTFLOW  
HOURS

TIME OF  
FAILURE  
HOURS

0.50  
1.00

1238.29  
1236.65

0.0  
0.0

906.  
1030.

2354.  
5716.

0.0  
0.0

44.50  
43.50


0.0  
0.0

APPENDIX D  
STABILITY COMPUTATIONS





SCS-357  
Continuation of Sheet 1 of 2  
Little Choconut Creek #2-C  
New York




[illegible]

**MATERIALS TESTING REPORT** **U. S. DEPARTMENT of AGRICULTURE SOIL CONSERVATION SERVICE** **TRIAxIAL SHEAR TEST**PROJECT and STATE LITTLE CHOCONUT CREEK # 20 NEW YORK SAMPLE LOCATION EMERGENCY SPILLWAYFIELD SAMPLE NO. 201.1 DEPTH 2.0 - 10.0' GEOLOGIC ORIGIN GLACIAL TILLTYPE OF SAMPLE DISTURBED TESTED AT LINCOLN APPROVED BY LPD DATE 11-5-65

INDEX TEST DATA				SPECIMEN DATA		TYPE OF TEST
USCS <u>GC GM</u>	LL <u>24</u>	PI <u>5</u>	% FINER (mm): 0.002 <u>6</u> ; 0.005 <u>12</u>	HEIGHT <u>8.0</u> "	DIAMETER <u>4.0</u> "	
	0.075 (#200) <u>40</u>		G <sub>s</sub> (+4) <u>2.70</u> ; G <sub>s</sub> (+4) <u>2.73</u>	MATERIALS TESTED PASSED <u>3/4"</u> SIEVE		UU <input type="checkbox"/>
STANDARD: $\gamma_d$ MAX. <u>116.5</u> pcf; $w_0$ <u>11.5</u> %			MODIFIED: $\gamma_d$ MAX. _____ pcf $w_0$ _____ %	METHOD OF PREPARATION <u>STATIC</u>		CU <input type="checkbox"/>
				<u>MOLDED IN 4 LIFTS</u>		CU <input checked="" type="checkbox"/>
				MOLDING MOISTURE <u>13.7</u> %		CD <input type="checkbox"/>
				MOLDED AT _____ % OF $\gamma_d$ MAXIMUM		

DRY DENSITY		MOISTURE CONTENT, %			TIME OF CONSOLIDATION (hrs.)	MINOR PRINCIPAL STRESS $\sigma_3$ (psi)	DEVIATOR STRESS $\sigma_1 - \sigma_3$ (psi)	AXIAL STRAIN AT FAILURE (%)
INITIAL pcf <input checked="" type="checkbox"/> g/cc <input type="checkbox"/>	CONSOLIDATED pcf <input checked="" type="checkbox"/> g/cc <input type="checkbox"/>	START OF TEST	DEG. OF SAT. AT START OF TEST	END OF TEST				
121.7	122.6	13.7	95.1	12.9	16.83	10	31.7	5.0
123.0	126.1	13.9	100.0	12.6	67.83	23.5	60.9	6.1
123.0	125.5	13.5	97.1	12.5	64.25	40	106.4	7.0




REMARKS

<b>MATERIALS TESTING REPORT</b>	U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	<b>TRIAXIAL SHEAR TEST</b> with pore pressure measured
-------------------------------------	--	---


PROJECT AND STATE <u>LITTLE PATENT CREEK NO. 20 NEW YORK</u>	SAMPLE LOCATION <u>EMERGENCY SPILLWAY</u>
TYPE OF SAMPLE	TESTED AT <u>SML LINCOLN</u>
	APPROVED BY <u>LPD</u>
	DATE <u>11-5-65</u>

MINOR PRINCIPAL STRESS, $\sigma_3$ (psi)	PORE PRESSURE, u (psi)	EFFECTIVE MINOR PRINCIPAL STRESS, $\bar{\sigma}_3$ (psi)	DEVIATOR STRESS, $\sigma_1 - \sigma_3$ (psi)	FAILURE CRITERIA	STRAIN AT FAILURE, e (%)
12	-0.3	10.3	31.7	Maximum Stress Ratio	5.0
23.5	2.3	21.2	60.8		6.1
40	3.6	36.4	106.4		7.0




REMARKS

<b>MATERIALS TESTING REPORT</b>		<b>U. S. DEPARTMENT of AGRICULTURE SOIL CONSERVATION SERVICE</b>		<b>COMPACTION AND PENETRATION RESISTANCE</b>	
PROJECT and STATE <u>Little Chocanut Creek #2-C New York</u>					
FIELD SAMPLE NO. <u>201.1</u>		LOCATION <u>Emergency Spillway</u>			DEPTH <u>2'-10'</u>
GEOLOGIC ORIGIN <u>Glacial Till</u>		TESTED AT <u>SML Lincoln</u>		APPROVED BY <u>LPD</u>	DATE <u>11-5-65</u>
CLASSIFICATION <u>GC-GM</u> LL <u>24</u> PI <u>5</u>				CURVE NO. <u>1X</u> OF <u>3X</u>	
MAX. PARTICLE SIZE INCLUDED IN TEST <u>&lt; 3/4"</u>				STD. (ASTM D-698) <input checked="" type="checkbox"/> ; METHOD <u>C</u>	
SPECIFIC GRAVITY (G <sub>s</sub> ) { MINUS NO. 4 <u>2.70</u> PLUS NO. 4 <u>2.73</u>				MOD. (ASTM D-1557) <input type="checkbox"/> ; METHOD _____	
				OTHER TEST <input type="checkbox"/> (SEE REMARKS)	



REMARKS

<b>MATERIALS TESTING REPORT</b>		<b>U. S. DEPARTMENT of AGRICULTURE SOIL CONSERVATION SERVICE</b>		<b>COMPACTION AND PENETRATION RESISTANCE</b>	
PROJECT AND STATE <u>Little Chocoma Creek #2-C New York</u>					
FIELD SAMPLE NO. <u>205.1</u>		LOCATION <u>Emergency Spillway</u>			DEPTH <u>2'-13'</u>
SOURCE OF ORIGIN <u>Glacial Till</u>		TESTED AT <u>SML Lincoln</u>		APPROVED BY <u>LPD</u>	DATE <u>11-5-65</u>
CLASSIFICATION <u>GC-GM</u> LL <u>27</u> PI <u>6</u>				CURVE NO. <u>2X</u> OF <u>3X</u>	
MAX. PARTICLE SIZE INCLUDED IN TEST <u>&lt; #4"</u>				STD. (ASTM D-698) <input checked="" type="checkbox"/> METHOD <u>C</u>	
SPECIFIC GRAVITY (G <sub>s</sub> ) { MINUS NO. 4 <u>2.69</u> PLUS NO. 4 <u>2.74</u>				MOD. (ASTM D-1557) <input type="checkbox"/> METHOD _____	
				OTHER TEST <input type="checkbox"/> (SEE REMARKS)	



REMARKS


<b>MATERIALS TESTING REPORT</b>	<b>U. S. DEPARTMENT of AGRICULTURE SOIL CONSERVATION SERVICE</b>	<b>COMPACTION AND PENETRATION RESISTANCE</b>
-------------------------------------	--	--

PROJECT and STATE Little Choconut Creek #12C New York

FIELD SAMPLE NO <u>207.1</u>	LOCATION <u>Emergency Spillway</u>	DEPTH <u>2'-10'</u>
---------------------------------	---------------------------------------	------------------------

GEOLOGIC ORIGIN <u>Glacial Till</u>	TESTED AT <u>SML Lincoln</u>	APPROVED BY <u>LPD</u>	DATE <u>11-5-65</u>
--	---------------------------------	---------------------------	------------------------

CLASSIFICATION _____ LL _____ PI _____	CURVE NO. <u>3X</u> OF <u>3X</u>
MAX. PARTICLE SIZE INCLUDED IN TEST <u>&lt; 3/4"</u>	STD. (ASTM D-698) <input checked="" type="checkbox"/> METHOD <u>C</u>
SPECIFIC GRAVITY (G <sub>s</sub> ) {	MOD. (ASTM D-1557) <input type="checkbox"/> METHOD _____
	OTHER TEST <input type="checkbox"/> (SEE REMARKS)
MINUS NO. 4 <u>2.71</u>	
PLUS NO. 4 <u>2.72</u>	



REMARKS



APPENDIX E

REFERENCES

## HYDRAULICS

Chow, Ven Te, 1959, Open Channel Hydraulics, McGraw Hill.

King, H.W. and E.F. Brater, 1963, Handbook of Hydraulics, 5th Edition, McGraw-Hill

### U.S. Army Corps of Engineers:

HEC-1 Flood Hydrograph Package - Dam Safety Version, September 1978.

Engineering Manual 1110-2-1405; Flood-Hydrograph Analyses and Computations, August 1959.

### U.S. Department of Agriculture, Soil Conservation Service:

National Engineering Handbook; Section 4 - Hydrology, August 1972.

### U.S. Department of Commerce; Weather Bureau:

Hydrometeorological Report No. 33: Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 Square Miles and Durations of 6,12,24, and 48 Hours, April 1956.

### U.S. Department of the Interior:

BUREC, 1977, Design of Small Dams, 2nd Ed. (rev. reprint).

USGS, 1980, Water Resources Data For New York, Western New York, USGS Water Data Report NY-80-3.

APPENDIX F  
PREVIOUS INSPECTION REPORTS

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION  
DAM INSPECTION REPORT  
(By Visual Inspection)

<u>Dam Number</u>	<u>River Basin</u>	<u>Town</u>	<u>County</u>	<u>Hazard Class*</u>	<u>Date &amp; Inspector</u>
96A-3619	Susq.	Haire	Broome	B	5/28/76 KDH

Type of Construction

- ☐ Earth w/concrete spillway  
☒ Earth w/drop inlet ~~pipe concrete~~  
☐ Earth w/stone or riprap spillway  
☐ Concrete  
☐ Stone  
☐ Timber

Use

- ☐ Water Supply  
☒ ~~Dam~~ Flood Control  
☐ Recreation  
☐ Fish and Wildlife  
☐ Farm Pond  
☐ No Apparent Use-Abandoned

Estimated Impoundment Size

- ☐ 1-5 acres  
☐ 5-10 acres  
☒ Over 10 acres *CS MAX.*

Estimated Height of Dam above Streambed

- ☐ Under 10 feet  
☐ 10-25 feet  
☒ Over 25 feet *59'*

Condition of Spillway

- ☒ Service satisfactory  
☐ In need of repair or maintenance  
☒ Auxiliary satisfactory  
☐ In need of repair or maintenance

Explain: \_\_\_\_\_

Condition of Non-Overflow Section

- ☒ Satisfactory  
☐ In need of repair or maintenance Explain: \_\_\_\_\_

Condition of Mechanical Equipment

- ☒ Satisfactory  
☐ In need of repair or maintenance Explain: \_\_\_\_\_

Evaluation (From Visual Inspection)

- ☒ No defects observed beyond normal maintenance  
☐ Repairs required beyond normal maintenance

\*Explain Hazard Class, if Necessary \_\_\_\_\_


APPENDIX G

DRAWINGS


DAM  
SITE



VICINITY MAP  
LITTLE CHOCONUT WATERSHED SITE 2C DAM  
I.D. NO. NY 722



**TOPOGRAPHIC MAP  
LITTLE CHOCONUT WATERSHED  
SITE 2C DAM  
I.D. No. NY 722**






AS BUILT

LEGEND

- OF STREAM
- CONTOUR LINES
- EXISTING FENCE LINES
- TRAVERSE LINE STATIONS
- BUILDINGS
- DIRT ROAD
- SEDIMENT POND
- CREST OF EMBANKMENT SPILLWAY
- DESIGN HIGH WATER
- EDGE OF WOODS & BRUSH
- BENCH MARK
- CONSTRUCTION LIGHT
- POWER LINE



AS BUILT 12/12/68  
FINCH HOLLOW, LITTLE CHOCONUT &  
TROUT BROOK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO 2-C  
LITTLE CHOCONUT CREEK  
PLAN OF STORAGE AREA

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

DESIGNED BY	L. HORTON	DATE	10/68
ENGINEER	J. BLICK	DATE	10/68
PROJECT	W. VULFE	DATE	10/68
TRACED		DATE	
CHECKED	J. H. BULL	DATE	10/68
APPROVED		DATE	


NO. 100-1000

### GENERAL NOTES

1. AREAS UNDER DAM, DYE, EMERGENCY SPILLWAY AND SUPPLEMENTAL BORROW AREA TO BE CLEARED AND GRUBBED. LIMITS TO BE CLEARED AND GRUBBED SHALL BE AS STATED IN THE FIELD BY THE ENGINEER (SPEC. 8A)
2. AREA UPSTREAM FROM DAM AND BELOW ELEVATION 1201.0 (HGL) AND DESIGNATED WASTE AREAS SHALL BE CLEARED. LIMITS OF AREA TO BE CLEARED SHALL BE AS STATED IN THE FIELD BY THE ENGINEER (SPEC. 8B)
3. BOTTOM SECTION OF EMERGENCY SPILLWAY FROM STATION 445 TO STATION 623 TO BE COVERED WITH 12" OF TOPSOIL. ALL ADDITIONAL TOPSOIL THAT IS SUITABLE FOR USE WILL BE INCORPORATED WITHIN THE SLOPES OF THE EARTHFILL AS DIRECTED BY THE ENGINEER

### INSTRUCTIONS FOR FOUNDATION AND ABUTMENT

1. AFTER STRIPPING EXCAVATE THE FLOOD PLAIN SETS FROM WITHIN THE LIMITS OF THE FOUNDATION OF THE DAM (COMMON ELEVATION) THE LIMITS AND DEPTHS OF THE EXCAVATION TO BE DETERMINED BY CONSTRUCTION BY THE ENGINEER IN THE FIELD
2. ABUTMENTS SHALL BE SLOPED TO 8:1 OR FLATTER (COMMON ELEVATION)



TYPICAL SECTION OF DAM

NOT TO SCALE

EARTH FILL REQUIREMENTS					
MATERIAL	MAX. ROCK SIZE	MAX. LIFT	REDUCED WATER CONTENT	COMPACTION	
				CLIPS	TEST
DIRTY GRAVELS FROM EMERGENCY SPILLWAY & SUPPLEMENTAL BORROW AREA REPRESENTED BY TO 1" FROM 10" TO 12" TO 25% FROM 10" TO 12" TO 2" FROM 12" TO 15"	6"	4"	2 PERCENTAGE PTS BELOW TO 2 PERCENTAGE PTS ABOVE OF "W.M."	A	95% ABT

1. MAXIMUM LIFT THICKNESS PRIOR TO COMPACTION
  2. WATER CONTENT AT TIME OF COMPACTION
  3. FOR TYPICAL COMPACTION CURVES SEE SHEET 12
- NOTE THE FOUNDATION SURFACE THROUGH THE SPACE BETWEEN THE DAM SHALL BE EXCAVATED TO A DEPTH OF 6' MIN. AND COMPACTIONED PRIOR TO PLACEMENT OF FILL MATERIAL

# FOR FOUNDATION AND ABUTMENT TREATMENT

AS BUILT

NOTE - FOR LEGEND SEE SHEETS

STRIPPING (EARTH, THE FLOOD PLAN FROM WITHIN THE LIMITS OF THE FOUNDATION OF DAM (COMMON EXCAVATION) THE LIMITS OF THE EXCAVATION TO BE DETERMINED AT THE TIME OF CONSTRUCTION BY THE ENGINEER IN THE FIELD. LIMITS SHALL BE SLOPED TO 8:1 OR FLATTER (COMMON EXCAVATION)



SHEET	RED D WATER CONTENT	COMPACTION	
		CLP-S	DEFINITION
1	2 PERCENTAGE PTS BELOW TO 2 PERCENTAGE PTS ABOVE OF 100%	A	95% MAX DENSITY BY ASTM D698, METHOD C

5' CONTOUR INTERVAL



SCALE

AS BUILT 12/2/68

FINCH HOLLOW, LITTLE CHOCONUT & TROUT BROOK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO 2-C  
LITTLE CHOCONUT CREEK  
PLAN OF STORAGE AREA

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Designed by J. M. ZUPLO	Drawn by W. POLTON	Checked by J. M. ZUPLO	Approved by J. M. ZUPLO
Scale 1" = 100'	Scale 1" = 100'	Scale 1" = 100'	Scale 1" = 100'
NY-2018-P			

NO. 2018-P


NO. 2018-P

SHEET 2  
THE SPACE BETWEEN  
A DEPTH OF 6 INCHES  
OF THE MATERIAL

275 ALONG DSH WINDAL ON NORTH SIDE OF  
UTILITY POLE 2.3 ABOVE GROUND 330'  
NE ALONG DIRT ROAD FROM INTERSECTION  
W. TH NEW IRELAND ROAD

SCS ALUM DISC 8 INAIL N. 26' 22 IN.  
WHITE PINE 15 ABOVE GRADING 22' N  
OF UTILITY POLE E 161' 8" AND 30 FT.  
E OF S. OF NEW HAVEN ROAD

451: 452



# AS BUILT

## LEGEND

- DESIGN HIGH WATER
- CREST OF EMERG. SPILL.
- SEDIMENT POOL
- E. OF STREAM
- CONTOUR LINES
- WOODS LINE
- BENCH MARK
- TRAVERSE STATIONS
- DIRT ROAD
- BUILDINGS
- SPUR ROAD
- DRILL HOLE
- TEST PIT
- TEST PIT
- CONSTRUCTION LIGHT
- POWER LINE

## LAYOUT DATA

## CURVE I

$\Delta$  58° 46' T 109.80  
 R 195' E 28.19  
 D 29° 23' M 23.08  
 L 200'

E. STATION	DEFLECTION	DIST. FROM PC
2+00	0	0
1+85	3° 40'	21.94
1+60	7° 21'	49.89
1+35	11° 01'	74.23
1+10	14° 41'	98.86
0+85	18° 22'	122.89
0+60	22° 02'	146.31
0+35	25° 42'	169.19
0+10	29° 23'	191.35

## LAYOUT DATA

## CURVE II

$\Delta$  51° 24' T 93.85  
 R 195' E 21.41  
 D 29° 23' M 19.24  
 L 174.95'

E. STATION	DEFLECTION	DIST. FROM PC
4+75	0	0
4+50	3° 40'	21.94
4+25	7° 21'	49.89
4+00	11° 01'	74.23
3+75	14° 41'	98.86
3+50	18° 22'	122.89
3+25	22° 02'	146.31
3+00	25° 42'	169.19

0 10 25 50 100 FEET  
SCALE

AS BUILT 10/2/68  
 FINCH HOLLOW, LITTLE CHOCONUT &  
 TROUT BROOK WATERSHED PROJECT  
 FLOODWATER RETARDING DAM NO 2-C  
 LITTLE CHOCONUT CREEK  
 PLAN OF STRUCTURAL WORKS

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

DESIGNED BY	DATE	APPROVED BY	DATE
W. C. HOBBS	3/68		
W. C. HOBBS	3/68		
W. C. HOBBS	3/68		
W. C. HOBBS	3/68		

2' CONTOUR INTERVAL

1280

1260

1240

1220

1200

1180

1+00

2+00


3+00

4+00

5+00

PROFILE ALONG CENTERLINE  
(FACING DAM)

0 10 20 30 40 50 60 70 80 90 100  
HORIZONTAL SCALE IN FEET



TYPICAL SECTION OF EMERGENCY SPILLWAY @ A OF LEVEL SECTION  
(TYPICAL FROM STA 1+75 TO STA 2+25 EXCAVATION LIMITS TO DESIGN BOTTOM FROM STA 0+32 TO STA 1+25)

NOTE:  
FOR TYPICAL SECTION OF LEVEE  
ALONG EMERGENCY SPILLWAY  
EXIT CHANNEL SEE SHEET 5

ELEV 1231

160.0'

ELEV 1230

TP-6

(6M)

APPROXIMATE STRIPPED GROUND LINE

APPROXIMATE BOTTOM OF CUTT  
TRENCH. FINAL DEPTH TO BE  
DETERMINED IN THE FIELD AT THE  
TIME OF CONSTRUCTION BY  
THE ENGINEER

STRIPPED GROUND



SECTION OF CUTT TRENCH AT  
STA 6+00 TYPICAL FROM STA 4+40  
TO 5+50 AND 8+50 TO 10+40

SECTION OF CUTT TRENCH  
STA 6+75 TYPICAL FROM STA  
TO 7+00 AND 8+00 TO 9+00

TRANSITION  
FROM 2 TO 1.5

OF EMERGENCY SPILLWAY  
@ A OF DAM STA 3+40

16.00

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)

(6M)


(6M)

(6M)

# AS BUILT



SECTION OF DITCH TRENCH AT STA 6-75 TYPICAL FROM STA 6-50 TO 7-00 AND 8-50 TO 9-50





SECTION OF DITCH TRENCH AT STA 8-00 TYPICAL FROM STA 7-00 TO 7-50 AND 7-75 TO 8-00




SECTION OF DITCH TRENCH AT STA 7-62 TYPICAL FROM STA 7-50 TO 7-75

CONSTRUCTION ELEVATIONS





AS BUILT 12/2/68  
FINCH HOLLOW, LITTLE CHOCONUT &  
TROUT BROOK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO. 2-C  
LITTLE CHOCONUT CREEK  
PROFILES


J. M. DAVIS 1/68  
D. YOLTON 2/68  
J. M. DAVIS 7/68 NY-308-4



PROFILE ALONG 4 OF EMERGENCY SPILLWAY




PROFILE ALONG 6 OF LEVEE






**AS BUILT**

STA 1+00 TO 1+15 - 2:1 SS, 8'-10"  
 STA 1+15 TO 1+18 - TRANSITION  
 STA 1+18 TO 3+96 - 2:1 SS, 8'-10"  
 STA 3+96 TO 4+44 - 4:1 SS, 8'-10"  
 STA 4+44 TO 4+68 - TRANSITION  
 STA 4+68 TO 4+86 - 1:1 SS, 8'-10"





**TYPICAL SECTION OF PRINCIPAL SPILLWAY EXCAVATION**





NOTE: EXCAVATE SLOTS 12'-0" x 2'-0"

**PRINCIPAL SPILLWAY EXCAVATION AT ANTI-SLOPE COLLARS**



**PROFILE ALONG C OF PRINCIPAL SPILLWAY**



**TYPICAL SECTION OF LEVEE  
 (ALONG EMERGENCY SPILLWAY CHANNEL)**


**AS BUILT 1944/45**  
 FINCH HOLLOW, LITTLE CHOCONUT &  
 TROUT BROOK WATERSHED PROJECT  
 FLOODWATER RETARDING DAM NO 2-C  
 LITTLE CHOCONUT CREEK  
 PROFILES

U.S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE

L. HIBBON  
 J. HUER  
 W. YOLTON

1/56  
 2/56

J. M. ZURLO  
 7/56  
 NY-2018-P



AD-A109 797

METCALF AND EDDY OF NEW YORK INC NY

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. LITTLE CHOCONUT WATERSHED SITE 2C --ETC(U)

SEP 81 G P FULTON

DACW51-81-C-0044

NL


UNCLASSIFIED

2 of 2

AD-A  
109 797



END  
DATE  
FILMED  
02-82  
DTIC




MICROCOPY RESOLUTION TEST CHART  
NBS 1010-A (ANSI/ISO #2)

# AS BUILT


## DRAINAGE SYSTEM NOTES

1. ALL DRAIN PIPE SHALL CONFORM TO SPECIFICATION NO. 600 SHALL BE 12" DIA. SHARP 1" CLASS 1 MANHOLE OR CLASS 2 MANHOLE TYPE A FULLY BITUMINOUS COATED PERFORATED PIPE.
2. USE A MINIMUM OF 2" OF DRAIN FILL AROUND PIPE.
3. THE PROFILES OF THE BOTTOM OF ALL EXCAVATIONS AS SHOWN ARE ONLY APPROX. THE REQUIRED FINISHED GRADES WILL BE ESTABLISHED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE ENGINEER.

SECTION E-E




PLAN OF OUTLET DRAIN  
(NOT TO SCALE)



TYPICAL SECTION ALONG OUTLET DRAIN

SECTION B-B & C-C





## GRAIN SIZE DISTRIBUTION GRAPH FOR DRAIN FILL



FROM HOLLOW, LITTLE CHOONUT & TROUT BROOK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO. 2-C  
LITTLE CHOONUT CREEK  
DRAINAGE SYSTEM DETAILS

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

BY L. H. BOSTON 6/56  
BY W. VOLTON 6/56  
BY J. M. ZURLO 7/56 NY-2018-P



# AS BUILT

2" OF OUTLET CHANNEL  
BOTTOM BOTTOM  
APPROX LENGTH 212  
BOTTOM SLOPE 1:1  
SIDE SLOPE 1:1

STATION	OUTLET	WATER 30' DIA PIPE	SLOPE
0+00	0	1178.50	1:1
0+10	16	1178.45	1:1
0+20	28	1178.77	1:1
0+30	44	1179.93	1:1
0+40	60	1179.08	1:1
0+50	76	1179.84	1:1
0+60	92	1179.59	1:1
0+70	108	1179.59	1:1
0+80	124	1179.70	1:1
0+90	140	1179.81	1:1
1+00	156	1180.04	1:1
1+10	172	1180.11	1:1
1+20	188	1180.51	1:1
1+30	204	1180.37	1:1
1+40	220	1180.41	1:1
1+50	236	1180.59	1:1
1+60	252	1180.60	1:1
1+70	268	1180.70	1:1
1+80	284	1180.80	1:1

NOTE ABOVE DIMENSIONS FOR LENGTH OF PIPE AND APPROX. NEUTRAL LENGTHS INCLUDE CREEP

STATION	WATER 30' DIA PIPE	WATER 30' DIA PIPE
0+00	1178.50	1178.50
0+10	1178.45	1178.45
0+20	1178.77	1178.77
0+30	1179.93	1179.93
0+40	1179.08	1179.08
0+50	1179.84	1179.84
0+60	1179.59	1179.59
0+70	1179.59	1179.59
0+80	1179.70	1179.70
0+90	1179.81	1179.81
1+00	1180.04	1180.04
1+10	1180.11	1180.11
1+20	1180.51	1180.51
1+30	1180.37	1180.37
1+40	1180.41	1180.41
1+50	1180.59	1180.59
1+60	1180.60	1180.60
1+70	1180.70	1180.70
1+80	1180.80	1180.80

12" NEAR WATER PIPE  
2" 12" SECTIONS  
SECTION  
PROCT. RING BALL FITTING FOR 12" WALL  
LENGTH 285.33"  
HEAD 57"  
10.12 LBS. PER LIN. FT. BASED ON O.D. OF 317  
MIN. EDGE BEARING STRENGTH FOR 0.001 CANAL  
1.323 LBS. PER LIN. FT. FOR PRESTRESSED PIPE  
(MIN. 2.5")

## PIPE SUPPLIERS NOTE

OUTSIDE OF SPICT RING WITH CONCRETE  
IN THE SECTION

## RIPRAP NOTE

RIPRAP ALONG OUTLET CHANNEL SHALL BE WELL  
GRADED FROM A MAX. SIZE OF 24" TO A MIN. OF 3"  
AND SHALL BE LAID ON 12" OF BEDDING.

BEDDING SHALL MEET THE GRADATION REQUIREMENTS  
FOR DAM FILL AS SHOWN ON SHEET I.

## SECTION A-A

IMPACT DAM MOUNT CONC  
DETAILS SHEET 12

INVERT EL. 1178.5  
EL. 1172.2

12" RIPRAP 30'  
ABOVE CHANNEL BOTTOM

8" 30" 25"  
20" 10" 10"  
10" 10" 10"

## AS BUILT AS/1/1/1

USE THIS SHEET FOR PIPE CONDUITS  
FURNISHED IN 4.0' SECTIONS

FINCH HOLLOW, LITTLE CHOCONUT &  
TROUT BROOK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO 2-C  
LITTLE CHOCONUT CREEK

PLAN-PROFILE OF PRINCIPAL SPILLWAY

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

1. BOTTOM

2. TOP

3. ANGLE

4. 20' 10"

NY-2000-P

1000 2 1/2 11 1/2 1/2 1/2 1/2



NOTE  
ENTIRE TRASH PACH EXCEPT  
ALUMINUM GRATING TO BE  
GALVANIZED IN ACCORDANCE WITH  
SPEC 119



### RISE R TRASH RACK DETAILS



# BILL OF MATERIALS

LOCATION	ITEM	SIZE	LENGTH	QUAN
100.0	1/2" DIA. BOLT	1/2"	10.0	20
100.0	1/2" DIA. NUT	1/2"	10.0	20
100.0	1/2" DIA. WASHER	1/2"	10.0	20
100.0	1/2" DIA. PIPE	1/2"	10.0	20

AS BUILT


1/2" DIA. BOLT  
THREADED PORTION  
2" EACH END

SHOULDER ON  
ANGLE IRON

BOLT DETAIL N° 1

1/2" Dia. Bolts  
w/ Max Nut And Washers  
11" Long

Drill 1/2" Dia  
Holes



10" Dia Pipe

SMALL ANIMAL GUARD DETAILS

AS BUILT 10/2/68


FINCH HOLLOW, LITTLE CHOCONUT &  
TROUT BROOK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO 2-C  
LITTLE CHOCONUT CREEK  
TRASH RACK & SMALL ANIMAL GUARD DETAILS  
U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

L. MITCHELL  
D. ANGEL

6/20  
6/20

6/20  
6/20


NY-2018-P



PLAN OF FLOOR SLAB TOP FACE


SYMMETRICAL ABOUT E

PLAN OF FLOOR SLAB TOP FACE




PLAN VIEW

1/2 PREFORMED JOINT FILLER, TYPE 2, MAY BE SPEC FOR PLACED BETWEEN DRAIN AND CHASSEL




SECTION ON E




SECTION THRU BAFFLE


SYMMETRICAL ABOUT E



SECTION C-C




HALF ISOMETRIC




SECTION THRU BAFFLE




SECTION B-B



SECTION A-A OUTSIDE FACE



SECTION A-A INSIDE FACE



SECTION ON E

# STEEL SCHEDULE

NO.	DESCRIPTION	QTY	SIZE	WEIGHT	UNIT	TOTAL WT.
1	REINFORCING STEEL	100	1/2"	1.10	LB	110.00
2	REINFORCING STEEL	100	3/4"	1.67	LB	167.00
3	REINFORCING STEEL	100	1"	2.41	LB	241.00
4	REINFORCING STEEL	100	1 1/4"	3.76	LB	376.00
5	REINFORCING STEEL	100	1 1/2"	4.41	LB	441.00
6	REINFORCING STEEL	100	2"	6.99	LB	699.00
7	REINFORCING STEEL	100	2 1/2"	10.99	LB	1099.00
8	REINFORCING STEEL	100	3"	15.00	LB	1500.00
9	REINFORCING STEEL	100	3 1/2"	19.00	LB	1900.00
10	REINFORCING STEEL	100	4"	23.00	LB	2300.00
11	REINFORCING STEEL	100	4 1/2"	27.00	LB	2700.00
12	REINFORCING STEEL	100	5"	31.00	LB	3100.00
13	REINFORCING STEEL	100	5 1/2"	35.00	LB	3500.00
14	REINFORCING STEEL	100	6"	39.00	LB	3900.00
15	REINFORCING STEEL	100	6 1/2"	43.00	LB	4300.00
16	REINFORCING STEEL	100	7"	47.00	LB	4700.00
17	REINFORCING STEEL	100	7 1/2"	51.00	LB	5100.00
18	REINFORCING STEEL	100	8"	55.00	LB	5500.00
19	REINFORCING STEEL	100	8 1/2"	59.00	LB	5900.00
20	REINFORCING STEEL	100	9"	63.00	LB	6300.00
21	REINFORCING STEEL	100	9 1/2"	67.00	LB	6700.00
22	REINFORCING STEEL	100	10"	71.00	LB	7100.00
23	REINFORCING STEEL	100	10 1/2"	75.00	LB	7500.00
24	REINFORCING STEEL	100	11"	79.00	LB	7900.00
25	REINFORCING STEEL	100	11 1/2"	83.00	LB	8300.00
26	REINFORCING STEEL	100	12"	87.00	LB	8700.00
27	REINFORCING STEEL	100	12 1/2"	91.00	LB	9100.00
28	REINFORCING STEEL	100	13"	95.00	LB	9500.00
29	REINFORCING STEEL	100	13 1/2"	99.00	LB	9900.00
30	REINFORCING STEEL	100	14"	103.00	LB	10300.00
31	REINFORCING STEEL	100	14 1/2"	107.00	LB	10700.00
32	REINFORCING STEEL	100	15"	111.00	LB	11100.00
33	REINFORCING STEEL	100	15 1/2"	115.00	LB	11500.00
34	REINFORCING STEEL	100	16"	119.00	LB	11900.00
35	REINFORCING STEEL	100	16 1/2"	123.00	LB	12300.00
36	REINFORCING STEEL	100	17"	127.00	LB	12700.00
37	REINFORCING STEEL	100	17 1/2"	131.00	LB	13100.00
38	REINFORCING STEEL	100	18"	135.00	LB	13500.00
39	REINFORCING STEEL	100	18 1/2"	139.00	LB	13900.00
40	REINFORCING STEEL	100	19"	143.00	LB	14300.00
41	REINFORCING STEEL	100	19 1/2"	147.00	LB	14700.00
42	REINFORCING STEEL	100	20"	151.00	LB	15100.00
43	REINFORCING STEEL	100	20 1/2"	155.00	LB	15500.00
44	REINFORCING STEEL	100	21"	159.00	LB	15900.00
45	REINFORCING STEEL	100	21 1/2"	163.00	LB	16300.00
46	REINFORCING STEEL	100	22"	167.00	LB	16700.00
47	REINFORCING STEEL	100	22 1/2"	171.00	LB	17100.00
48	REINFORCING STEEL	100	23"	175.00	LB	17500.00
49	REINFORCING STEEL	100	23 1/2"	179.00	LB	17900.00
50	REINFORCING STEEL	100	24"	183.00	LB	18300.00
51	REINFORCING STEEL	100	24 1/2"	187.00	LB	18700.00
52	REINFORCING STEEL	100	25"	191.00	LB	19100.00
53	REINFORCING STEEL	100	25 1/2"	195.00	LB	19500.00
54	REINFORCING STEEL	100	26"	199.00	LB	19900.00
55	REINFORCING STEEL	100	26 1/2"	203.00	LB	20300.00
56	REINFORCING STEEL	100	27"	207.00	LB	20700.00
57	REINFORCING STEEL	100	27 1/2"	211.00	LB	21100.00
58	REINFORCING STEEL	100	28"	215.00	LB	21500.00
59	REINFORCING STEEL	100	28 1/2"	219.00	LB	21900.00
60	REINFORCING STEEL	100	29"	223.00	LB	22300.00
61	REINFORCING STEEL	100	29 1/2"	227.00	LB	22700.00
62	REINFORCING STEEL	100	30"	231.00	LB	23100.00
63	REINFORCING STEEL	100	30 1/2"	235.00	LB	23500.00
64	REINFORCING STEEL	100	31"	239.00	LB	23900.00
65	REINFORCING STEEL	100	31 1/2"	243.00	LB	24300.00
66	REINFORCING STEEL	100	32"	247.00	LB	24700.00
67	REINFORCING STEEL	100	32 1/2"	251.00	LB	25100.00
68	REINFORCING STEEL	100	33"	255.00	LB	25500.00
69	REINFORCING STEEL	100	33 1/2"	259.00	LB	25900.00
70	REINFORCING STEEL	100	34"	263.00	LB	26300.00
71	REINFORCING STEEL	100	34 1/2"	267.00	LB	26700.00
72	REINFORCING STEEL	100	35"	271.00	LB	27100.00
73	REINFORCING STEEL	100	35 1/2"	275.00	LB	27500.00
74	REINFORCING STEEL	100	36"	279.00	LB	27900.00
75	REINFORCING STEEL	100	36 1/2"	283.00	LB	28300.00
76	REINFORCING STEEL	100	37"	287.00	LB	28700.00
77	REINFORCING STEEL	100	37 1/2"	291.00	LB	29100.00
78	REINFORCING STEEL	100	38"	295.00	LB	29500.00
79	REINFORCING STEEL	100	38 1/2"	299.00	LB	29900.00
80	REINFORCING STEEL	100	39"	303.00	LB	30300.00
81	REINFORCING STEEL	100	39 1/2"	307.00	LB	30700.00
82	REINFORCING STEEL	100	40"	311.00	LB	31100.00
83	REINFORCING STEEL	100	40 1/2"	315.00	LB	31500.00
84	REINFORCING STEEL	100	41"	319.00	LB	31900.00
85	REINFORCING STEEL	100	41 1/2"	323.00	LB	32300.00
86	REINFORCING STEEL	100	42"	327.00	LB	32700.00
87	REINFORCING STEEL	100	42 1/2"	331.00	LB	33100.00
88	REINFORCING STEEL	100	43"	335.00	LB	33500.00
89	REINFORCING STEEL	100	43 1/2"	339.00	LB	33900.00
90	REINFORCING STEEL	100	44"	343.00	LB	34300.00
91	REINFORCING STEEL	100	44 1/2"	347.00	LB	34700.00
92	REINFORCING STEEL	100	45"	351.00	LB	35100.00
93	REINFORCING STEEL	100	45 1/2"	355.00	LB	35500.00
94	REINFORCING STEEL	100	46"	359.00	LB	35900.00
95	REINFORCING STEEL	100	46 1/2"	363.00	LB	36300.00
96	REINFORCING STEEL	100	47"	367.00	LB	36700.00
97	REINFORCING STEEL	100	47 1/2"	371.00	LB	37100.00
98	REINFORCING STEEL	100	48"	375.00	LB	37500.00
99	REINFORCING STEEL	100	48 1/2"	379.00	LB	37900.00
100	REINFORCING STEEL	100	49"	383.00	LB	38300.00

## BAR TYPES

## IMPACT BASIN QUANTITIES

### REINFORCING STEEL

NO 3 BARS 5020.7 LB 113.5 LB  
 NO 4 BARS 225.0 LB 11.7 LB  
 NO 7 BARS 820.0 LB 16.7 LB

### CONCRETE

REINFORCED 35.42 CU YDS

## AS BUILT

SEE SHEET 10 FOR CONSTRUCTION NOTES

DATE AS BUILT 10/1/68

FINCH HOLLOW, LITTLE CHOCONUT &  
 TROUT BROOK WATERSHED PROJECT  
 FLOODWATER RETARDING DAM NO 2-C  
 LITTLE CHOCONUT CREEK  
 IMPACT BASIN DETAILS

U.S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE

Prepared by  
 Fred B. Phum  
 in charge

W. H. BORDMAN  
 District Engineer

Checked by  
 E. L. Cady

Drawn by

Scale

Notes

Revised

Project

Sheet

NY-508-P